CHANDERNAGORE MUNICIPAL CORPORATION

No.IA/Tend/2025-26/194/B

Dated. 11.11.2025

URGENT NOTICE INVITING QUOTATION:

Fund; Line Dept. Govt. Grant.

invited from the experienced, resourceful and interested Vendors/Suppliers/Contractors to complete the work of the following items required for Electric Dept. under the control of this Corporation individually or unanimously. Vendors/Suppliers/Contractors may participate for both individually or unanimously of the following works.

Quotations are to be given on or before 18.11.2025 within 3 p.m. and will be opened on the same day at 3.30 p.m. Rates should be inclusive of all the taxes and other incidental charges if any. In case of accepted tenderers whose rates have been accepted, fails to supply the required items within the stipulated date & time, necessary items will be purchased from the available sources and the difference in cost will be recovered from the tenderers. The Corporation reserves the right to accept or reject any tender without assigning any reason whatsoever.

Description of the Items	Booth	Sl. No.	Ward No.	Quantity Required	Rate Required
G. Street light in front		06	18	One Job	Entire Work
Arrangement of two nos of Street light in none	12.				
of Nataraj Club at Sasan Kali Palli.	120	06	18	One Job	Entire Work
Installation of electric pole with light upto	10				
house of Milan Pramanik at Keorapara 3 no.					
Lichutala.		0.1	11	One Joh	Entire Work
Installation of light infront of house of Sekh	105	01	11	One soo	
Arshan at Kuthir Ghat at Urdibazar.				One Tele	Entire Work
Installation of light opposite infront of house	105	06	11	One Job	Entire Work
of Pachugonal at Pilkhana.					T 11 "XXI -1-
Increase illumination of light opposite side of	104	08	11	One Job	Entire Work
The Medical G T Pood					
	Arrangement of two nos of Street light in front of Nataraj Club at Sasan Kali Palli. Installation of electric pole with light upto house of Milan Pramanik at Keorapara 3 no. Lichutala. Installation of light infront of house of Sekh Arshan at Kuthir Ghat at Urdibazar. Installation of light opposite infront of house of Pachugopal at Pilkhana.	Arrangement of two nos of Street light in front of Nataraj Club at Sasan Kali Palli. Installation of electric pole with light upto house of Milan Pramanik at Keorapara 3 no. Lichutala. Installation of light infront of house of Sekh Arshan at Kuthir Ghat at Urdibazar. Installation of light opposite infront of house of Pachugopal at Pilkhana. Increase illumination of light opposite side of 104	Arrangement of two nos of Street light in front of Nataraj Club at Sasan Kali Palli. Installation of electric pole with light upto house of Milan Pramanik at Keorapara 3 no. Lichutala. Installation of light infront of house of Sekh Arshan at Kuthir Ghat at Urdibazar. Installation of light opposite infront of house of Pachugopal at Pilkhana. Increase illumination of light opposite side of 104 08	Arrangement of two nos of Street light in front of Nataraj Club at Sasan Kali Palli. Installation of electric pole with light upto house of Milan Pramanik at Keorapara 3 no. Lichutala. Installation of light infront of house of Sekh Arshan at Kuthir Ghat at Urdibazar. Installation of light opposite infront of house of Pachugopal at Pilkhana. Increase illumination of light opposite side of 104 08 11	Arrangement of two nos of Street light in front of Nataraj Club at Sasan Kali Palli. Installation of electric pole with light upto house of Milan Pramanik at Keorapara 3 no. Lichutala. Installation of light infront of house of Sekh Arshan at Kuthir Ghat at Urdibazar. Installation of light opposite infront of house of Pachugopal at Pilkhana. Increase illumination of light opposite side of 104 08 11 One Job

Enclo: Estimate of all Works are attached herewith.

PAN, GST and Copy of Trade Enlistment Certificate are Mandatory in this regard.

5000 11111 VS Commissioner/Secretary/Finance Officer Chandernagore Municipal Corporation

Dated. 11.11.2025 No.IA/Tend/2025-26/194/B/1 (12)

Copy to :
1. Mayor

MMIC (Street Light / Education / Trade Licence / Health / W.W / Sports / Store & Garage) 3.

Commissioner/Secretary/Finance Officer

Engineer

A. O.

SAE (Elect) 7.

S.A.-1 Please publish in Office Website.

Office Notice Board

28/11/11/08 Commissioner/Secretary/Finance Officer Chandernagore Municipal Corporation`

CHANDERNAGORE MUNICIPAL CORPORATION <u>ESTIMATE</u>

L Dept

Estimated Cost:- Rs.41,479/-

Date of Completion: 7 days

Name of the work: Installation of electric pole with light upto house of Milan Pramanik at Keorapara 3 no. Lichutala
Under APAS Scheme -- Booth 120_sl no 6_w18

SL No	Description of Work	Qty	Uni	t Rate in Rs.	Amount
1	Supplying of Swaged Steel Tubular pole (IS 2713, Pt. II 1980) for following designation and of following dimensions 4 SWG;5.0 mtrs; 45 Kg	2	Nos		8432
	Ref: UDMA(E/M) (Vol 1) Schedule 2018, page-3,1 (b)				
1	Erection of Single Steel tubular pole of length as given below with/without sole plate & Cap etc. in CC foundation (Proportion and dimension indicated below), having 600x600x150 mm thick CC (4:2:1) base block below sole plate/pole with hard jhama metal including CC (6:3:1) muffing 0.30 mts. dia and 0.30 mts. above ground level including 3 mm thick neat cemented finish and GI earth bolt after making drilled holes etc. on pole & carriage of pole upto 1.6 Km from Store to work-site including filling up the excavated earth pit with shifted soil and ramming properly Upto 9.0 mtr. Size 0.6x0.6x1.70 mts		Nos	2835.00	5670.00
	Ref: PWD(Electrical) Schedule 2017, H-1, (A)1(a)				
3	Extra on items 1& 2 above, for providing CC (6:3:1) base block (around the pole) dimension 0.45x0.45x0.60 mt. above ground level, neatly cemented finish (3 mm thick), at the base pole (in lieu of CC muffing) suitable for alkathene/ polythene pipe entry as directed for street light wiring, incl. S & F 20cmx15cmx10cm GI Loop box, 16SWG & incl. drilled hole in pole	2	Nos	740.00	1480.00
1	Ref: PWD(Electrical) Schedule 2017, H-1, (A)3(a)(ii)				
4 c lo	Painting of Steel Tubular Pole of lengths and no. of coats of paint, as given below with ready mixed paint/primer of approved make, and orand incl. preparation of surface by sand paper/emery paper, leaning etc. for receiving fresh coat of paint (a) Upto 9.0 mtr. ong pole (i)1st coat of aluminium paint over 1 coat of RO priming (ii)2nd coat of aluminium paint over 1st coat	2	Nos	329.00	658.00
	Ref: PWD(Electrical) Schedule 2017, H-2, (A)4(a)				
5 5	upplying of 1.1 KV. Grade PVC insulated Conductor of following cables (make: Polycab/ Gloster/Havells/): 2 core 4sqmm	60	Mtr	73.00	4380.00
	ef: UDMA(E/M) Schedule 2018, page-13, 1(a)1)				
6 sa m	Laying of cable upto 2 core 25 sqmm on wall/surface incl. S & F MS addles with earthing attachment in 10 SWG GI (Hot Dip) Wire, aking holes etc. as necy. mending good damages and painting	60	Mtr 8	57.00	3420.00
R	ef: PWD(Electrical) Schedule 2017, F-1, 2(a)				

			mills to the		
	pply and delivery of 30 watt LED Street Light with pressure die st aluminium housing, IP66 protection, road way luminarie with ligh power LED as per the detail technical proposal specification & vendor list attached [Make-Crompton / Philips / Havells Warranty Period- 7 Years]	2	Nos	2179.46	4358.92
11	Ref: Rate Redrive		-		
8	Fixing outdoor type fluorescent/SV/MV light fitting on pole including S&F 40 mm dia x 1.68 mts. long GI Pipe (ISI-Medium) bracket with 40 mmx10 mm thick, MS clamp etc. and providing wiring with 2x1/1.40 PVC insulated and sheathed wire (single core) from loop box at the base of pole to light fiting through pole & bracket (without control switch) including making connections & painting	2	Nos	1335.00	2670.00
	Ref: PWD(Electrical) Schedule 2014, H-5,H(4)				
9	Supplying and fixing 240/415V MCB of Breaking capacity 10kA&C characteristics on din rail of existing DBs and necessary connection-6-32 A [Legrand / Schneider/ Crabtree]	2	Nos	157.00	314.00
	Ref: PWD(Electrical) Schedule 2017, D-6/7				
10	Earthing with 50mm dia GI pipe 3.64mm thick x 3.04mtrs long and 1x4SWG GI (Hot Dip) wire (4mtrs long), 13mm dia x 80mm long GI bolts, double nuts, double washers incl. S&F 15mm dia GI pipe protection (1mtr long) to be filled with bitumen partly under the ground level and partly above ground level driven to an average depth of 3.65mts below the ground level as below: by ISI-Medium GI pipe	2	Nos	1369.00	2738.00
	Ref:PWD Schedule (Electrical)2017, Page-G-1/2(a)				
	Sub Total		F	RS	34,120.92
	Add (@18%) Gst			S	6,141.77
	Sub Total		R	RS	40,262.69
	Add (@1%) Cess		R	S	402.63
	Total		R	s	40,665.31
	Add (@2%) Contingeny		R	S	813.31
	Total		R	S	41 478 62

SAE (ELECTRICAL)
CHANDERNAGORE MUNICIPAL CORPORATION

AE (MECHANICAL)
CHANDERNAGORE MUNICIPAL
CORPORATION

COMMISSIONER
CHANDERNAGORE MUNICIPAL CORPORATION

101 Pd

CHANDERNAGORE MUNICIPAL CORPORATION ESTIMATE

Estimated Cost:- Rs.31,628/- 31676/-

Date of Completion: 7 days

Name of the work :- Arrangement of two nos of Street light in front of Nataraj Club at Sasan Kali Palli Under APAS

Scheme -- Booth 124_sl no 6_w18

SL No	Description of Work	Qty	Un	it Rate in Rs.	Amount
1	Supplying of Swaged Steel Tubular pole (IS 2713, Pt. II 1980) for following designation and of following dimensions 410-SP-1; 7.0 mtrs: 62.00Kg	1	No		4216
	Ref: UDMA(E/M) (Vol 1) Schedule 2018, page-3,1 (d)				
	S/F double arm projected lamp bracket (Single pip bending) of 50mm (2") dia G.I. pipe (ISI medium) of 2.5 mtr long each having 105 degree curvature with reducing socket to be fitted at the top of the pole with bolts, nuts clamps etc. as required Ref: UDMA(E/M) (Vol 1) Schedule 2018, page-5, 23	1	No.	2491	4216
	Erection of Single Steel tubular pole of length as given below with/without sole plate & Cap etc. in CC foundation (P)				
3	(4:2:1) base block below sole plate/pole with hard jhama metal including CC (6:3:1) muffing 0.30 mts. dia and 0.30 mts. above ground level including 3 mm thick neat cemented finish and GI earth bolt after making drilled holes etc. on pole & carriage of pole upto 1.6 Km from Store to work-site including filling up the excavated earth pit with shifted soil and ramming properly Upto 0.0 mtr. Size 0.6x0.6x1.70 mts		No.	2835.00	2835.00
	Ref: PWD(Electrical) Schedule 2017, H-1, (A)1(a)				
n m st	Extra on items 1& 2 above, for providing CC (6:3:1) base block around the pole) dimension 0.45x0.45x0.60 mt. above ground level, eatly cemented finish (3 mm thick), at the base pole (in lieu of CC nuffing) suitable for alkathene/ polythene pipe entry as directed for creet light wiring, incl. S & F 20cmx15cmx10cm GI Loop box, 16SWG & incl. drilled hole in pole	1	No.	740.00	740.00
-	ef: PWD(Electrical) Schedule 2017, H-1, (A)3(a)(ii)				
br cle lor (ii	wen below with ready mixed paint/primer of approved make, and rand incl. preparation of surface by sand paper/emery paper, eaning etc. for receiving fresh coat of paint (a) Upto 9.0 mtr. ng pole (i)1st coat of aluminium paint over 1 coat of RO priming i)2nd coat of aluminium paint over 1st coat	1	No.	329.00	329.00
Re	ef: PWD(Electrical) Schedule 2017, H-2, (A)4(a)				
Su	pplying of 1.1 KV. Grade PVC insulated Conductor following cables (make: Polycab/ Gloster/Havells/): 2 core 4sqmm	20	Mtr	73.00	1460.00
	f: UDMA(E/M) Schedule 2018, page-13, 1(a)1)				
sac	aying of cable upto 2 core 25 sqmm on wall/surface incl. S & F MS ldles with earthing attachment in 10 SWG GI (Hot Dip) Wire, king holes etc. as necy. mending good damages and painting	20	Mtr 8	57.00	1140.00
Re	f: PWD(Electrical) Schedule 2017, F-1, 2(a)		-		

3	Supply and delivery of 45 watt LED Street Light with pressure die cast aluminium housing, IP66 protection, road way luminarie with high power LED as per the detail technical proposal specification & vendor list attached [Make-Crompton /Philips/ Havells Warranty Period- 7 Years]	2	No.	3579.46	7158.92
	Ref: Rate Redrive Fixing outdoor type fluorescent/SV/MV light fitting on pole including S&F 40 mm dia x 1.68 mts. long GI Pipe (ISI-Medium) bracket with 40 mmx10 mm thick, MS clamp etc. and providing wiring with 2x1/1.40 PVC insulated and sheathed wire (single core) from loop box at the base of pole to light fiting through pole & bracket (without control switch) including making connections & painting	2	No.	1335.00	2670.00
10	Ref: PWD(Electrical) Schedule 2014, H-5,H(4) Supplying and fixing 240/415 V MCB of Breaking capacity 10 KA & C characteristics on din rail of existing DBs and necessary connection 6-32 A SPN (Standard)	1	No.	444.00	444.00
11	Ref: PWD(Electrical) Schedule 2017, D-7/8 Earthing with 50mm dia GI pipe 3.64mm thick x 3.04mtrs long and 1x4SWG GI (Hot Dip) wire (4mtrs long), 13mm dia x 80mm long GI bolts, double nuts, double washers incl. S&F 15mm dia GI pipe protection (1mtr long) to be filled with bitumen partly under the ground level and partly above ground level driven to an average depth of 3.65mts below the ground level as below: by ISI-Medium GI pipe	1	No.	1369.00	1369.00
	Ref:PWD Schedule (Electrical)2017, Page-G-1/2(a)			RS	26,577.92
	Sub Total		-	RS	4,784.03
	Add (@18%) Gst			RS	31,361.95
	Sub Total			RS	265.78-31362
	Add (@1%) Cess			Rs	31,627.72 31675
	Total			Rs	31,628 31670

8-5-10.09.2025-SAE (ELECTRICAL)

CHANDERNAGORE MUNICIPAL CORPORATION

AE (MECHANICAL)

CHANDERNAGORE MUNICIPAL

CORPORATION

COMMISSIONER CHANDERNAGORE MUNICIPAL CORPORATION



CHANDERNAGORE MUNICIPAL CORPORATION ESTIMATE

Estimated Cost:- Rs. 4,605/-

Date of Completion: 7 days

Name of the work :- Installation of light infront of house of Sekh Arshan at Kuthir Ghat at Urdibazar Under
APAS Scheme -- Booth 105 sl no:-1 ward 11

SL No	Description of Work	Qty	Uni		n Amoun
1	Supply and delivery of 30 watt LED Street Light with pressure die cast aluminium housing, IP66 protection, road way luminarie with high power LED as per the detail technical proposal specification & vendor list attached [Make-Crompton/Philips / Havells Warranty Period- 7 Years]	1	No.	2179.46	2179.46
	Ref: Rate Redrive		-		
2	Fixing outdoor type fluorescent/SV/MV light fitting on pole including S&F 40 mm dia x 1.68 mts. long GI Pipe (ISI-Medium) bracket with 40 mmx10 mm thick, MS clamp etc. and providing wiring with 2x1/1.40 PVC insulated and sheathed wire (single core) from loop box at the base of pole to light fiting through pole & bracket (without control switch) including making connections & painting	1	No.	1335.00	1335.00
I	Ref: PWD(Electrical) Schedule 2017, H-5,H(4)			AND	
3 1	.5 sq.mm 'FR' stranded Copper Wire				
R	Ref: PWD(Electrical) Schedule 2017, K-2,sl no 70	20	Mtr	13.68	273.60
	7 - 3 - 3 - 3 - 3 - 3 - 3 - 3 - 3 - 3 -				
	Sub Total		F	RS	2 700 05
	Add (@18%) Gst		R		3,788.06
	Sub Total			S	681.85
	Add (@1%) Cess		R		4,469.91
	Total		R		44.70
_	Add (@2%) Contingency		R		4,514.61
	Total				90.29
					4,604.90

13.10. 2025 SAE (ELECTRICAL)

CHANDERNAGORE MUNICIPAL CORPORATION

AE (MECHANICAL) 13.10 .25

CHANDERNAGORE MUNICIPAL CORPORATION

COMMISSIONER

CHANDERNAGORE MUNICIPAL CORPORATION

CHANDERNAGORE MUNICIPAL CORPORATION Line Dept **ESTIMATE**

Estimated Cost:- Rs. 4,272/-

Date of Completion: 7 days

Name of the work :- Installation of light infront of house of Pachugopal at Pilkhana Under APAS Scheme -- Booth 105 sl no:-6 ward 11

Supply and delivery of 30 watt LED Street Light with pressure die cast aluminium housing, IP66 protection, road way luminarie with high power LED as per the detail technical proposal specification & 1 No. 2179.46 2179.46 Warranty Period- 7 Years] Ref: Rate Redrive Fixing outdoor type fluorescent/SV/MV light fitting on pole including S&F 40 mm dia x 1.68 mts. long GI Pipe (ISI-Medium) bracket with 40 mmx10 mm thick, MS clamp etc. and providing wiring with 2x1/1.40 PVC insulated and sheathed wire (single core) 1 No. 2179.46 2179.4 2179.4 No. 2179.46 2179.4 2179.4 2179.4 No. 2179.46	SL No	Description of Work	Qty	Unit	Rate in	
Fixing outdoor type fluorescent/SV/MV light fitting on pole including S&F 40 mm dia x 1.68 mts. long GI Pipe (ISI-Medium) bracket with 40 mmx10 mm thick, MS clamp etc. and providing wiring with 2x1/1.40 PVC insulated and sheathed wire (single core) from loop box at the base of pole to light fiting through pole & bracket (without control switch) including making connections & painting Ref: PWD(Electrical) Schedule 2017, H-5,H(4) Sub Total Add (@18%) Gst Sub Total RS 3,514.46 Add (@18%) Gst RS 632.60 Sub Total RS 4,147.06 Add (@1%) Cess RS Add (@2%) Contingency Total RS 83.77	1	vendor list attached Make-Crownton (Philipped Vision &				2179.40
bracket with 40 mmx10 mm thick, MS clamp etc. and providing wiring with 2x1/1.40 PVC insulated and sheathed wire (single core) from loop box at the base of pole to light fiting through pole & bracket (without control switch) including making connections & painting Ref: PWD(Electrical) Schedule 2017, H-5,H(4) Sub Total Add (@18%) Gst Sub Total RS 3,514.46 Add (@18%) Gst RS 4,147.06 Add (@1%) Cess RS 4,147.06 Add (@2%) Contingency Total RS 3,577		Ref: Rate Redrive				
bracket with 40 mmx10 mm thick, MS clamp etc. and providing wiring with 2x1/1.40 PVC insulated and sheathed wire (single core) from loop box at the base of pole to light fiting through pole & bracket (without control switch) including making connections & painting Ref: PWD(Electrical) Schedule 2017, H-5,H(4) Sub Total Add (@18%) Gst Sub Total RS 3,514.46 Add (@18%) Gst RS 4,147.06 Add (@1%) Cess RS 4,147.06 Add (@2%) Contingency Total RS 3,577		Fixing outdoor type fluorescent/SV/MV light fitting				
Add (@18%) Gst RS 3,514.46 Sub Total RS 4,147.06 Add (@1%) Cess RS 41.47 Total Rs 4,188.53 Add (@2%) Contingency RS 83.77	2	bracket with 40 mmx10 mm thick, MS clamp etc. and providing wiring with 2x1/1.40 PVC insulated and sheathed wire (single core) from loop box at the base of pole to light fiting through pole & pracket (without control switch) including making connections & painting	1	No.	1335.00	1335.00
Add (@18%) Gst RS 632.60 Sub Total RS 4,147.06 Add (@1%) Cess RS 41.47 Total Rs 4,188.53 Add (@2%) Contingency RS 83.77	-	Sub Total		PS		0.00
Sub Total RS 4,147.06 Add (@1%) Cess RS 41.47 Total Rs 4,188.53 Add (@2%) Contingency RS 83.77		Add (@18%) Gst				
Add (@1%) Cess RS 41.47 Total Rs 4,188.53 Add (@2%) Contingency RS 83.77		Sub Total				
Total Rs 4,188.53 Add (@2%) Contingency RS 83.77 Total		Add (@1%) Cess				
Add (@2%) Contingency RS 83.77	_	Total				
Total K3 83.77		Add (@2%) Contingency				
				KS		

SAE (ELECTRICAL) CHANDERNAGORE MUNICIPAL CORPORATION

AE (MECHANICAL) CHANDERNAGORE MUNICIPAL CORPORATION

COMMISSIONER CHANDERNAGORE MUNICIPAL CORPORATION

CORPORATION

CHANDERNAGORE MUNICIPAL CORPORATION <u>ESTIMATE</u>

Estimated Cost:- Rs. 4,694/-

Date of Completion: 7 days

Name of the work :- Increase illumination of light opposite side of Tosh Medical, G.T.Road Under

APAS Scheme -- Booth 104 sl no:-8 ward 11

SL No	Description of Work	Qty	Un	it Rate	A
1	high power LED as per the detail technical proposal specification of warranty Period- 7 Years	& 1	No.	2179.4	6 2179.4
	Ref: Rate Redrive				
	Fixing outdoor type fluorescent/SV/MV light fitting on pole including S&F 40 mm dia x 1.68 mts. long GI Pipe (ISI-Medium) bracket with 40 mmx10 mm thick, MS clamp etc. and providing wiring with 2x1/1.40 PVC insulated and sheathed wire (single core) from loop box at the base of pole to light fiting through pole & bracket (without control switch) including making connections & painting	1	No.	1335.00	1335.00
	Ref: PWD(Electrical) Schedule 2017 H.5 H(4)				
3	1.5 sq.mm FR' stranded Copper Wire				
1	Ref: PWD(Electrical) Schedule 2017, K-2,sl no 70	20	Mtr	13.68	273.60
2	Supply & Fixing 240V 16/20			-	
4 H	(Brand approved by EIC) on existing sheet metal switch board having bakelite/perspex top cover by screws after making housing for switch by cutting bakelite/perspex tover and making necessary connections as required sef: PWD(Electrical) Schedule 2017, E-5, sl no 14(b)	1	No.	73.00	73.00
-	Sub Total		RS	3	3,861.06
-	Add (@18%) Gst Sub Total		RS		694.99
	Add (@1%) Cess		RS		4,556.05
_	Total		RS		45.56
-	Add (@2%) Contingency		Rs		4,601.61
	Total		RS		92.03

25-09. 2025 SAE (ELECTRICAL)

CHANDERNAGORE MUNICIPAL CORPORATION

AE (MECHANICAL) CHANDERNAGORE MUNICIPAL CORPORATION

COMMISSIONER
CHANDERNAGORE MUNICIPAL CORPORATION