



CHANDERNAGORE MUNICIPAL CORPORATION

No.IA/Tend/2025-26/227

Dated. 28.11.2025

URGENT NOTICE INVITING QUOTATION:

Fund: APAS.

Sealed tenders are invited from the experienced, resourceful and interested Vendors/Suppliers/Contractors to complete the work of the following items required for Electric Dept. under the control of this Corporation individually or unanimously. Vendors/Supplier/Contractors may participate for both individually or unanimously of the following works.

Quotations are to be given on or before 05.12.2025 within 3 p.m. and will be opened on the same day at 3.30 p.m. Rates should be inclusive of all the taxes and other incidental charges if any. In case of accepted tenderers whose rates have been accepted, fails to supply the required items within the stipulated date & time, necessary items will be purchased from the available sources and the difference in cost will be recovered from the tenderers. The Corporation reserves the right to accept or reject any tender without assigning any reason whatsoever.

Sl. No.	Description of the Items	Booth No	Sl. No.	Ward No.	Quantity Required	Rate Required
1.	Installation of Bright LED Light on Electric Pole beside of house of Naren Bairagi at Surighat.	52	09	06	One Job	Entire Work
2.	Construction of guardwall, arrangement of light & renovation of drain adjacent to pond in front of the house of Ashu Das at jadu Ghosh Lane.	40	04	04	One Job	Entire Work
3.	Construction of boundary fencing in front of student's Club with installation of bright light at Jadu Ghosh Lane.	40	03	04	One Job	Entire Work
4.	Installation of bright LED Light in front of Panchanan Dey at kalachand Colony.	34	05	01	One Job	Entire Work
5.	Installation of bright LED Light on electric pole in front house of Gopal Karmakar at Guinbagan Area.	34	04	01	One Job	Entire Work
6.	Enhancement of illumination in front Sk. Sa'im at Surepukur Muslimpara.	34	03	01	One Job	Entire Work
7.	Installation of electric pole with bright LED light in front of Sri Nanda Bairagi at Bishaharitala Bye Lane.	33	10	01	One Job	Entire Work
8.	Enhancement of illumination in front of house of Shibu Bhowmick, Raju Mondal and Aviraj Mukherjee at Bishaharitala Purbapara.	33	05	01	One Job	Entire Work
9.	Arrangement of bright LED light in front house of Pathak at Dr. Gli. Kantapukur.	28	06	02	One Job	Entire Work
10.	Installation of Bright LED Light in front of house of Satish Pal at haridradanga.	25	05	01	One Job	Entire Work

Encl: Estimate of all Works are attached herewith.

PAN, GST and Copy of Trade Enlistment Certificate are Mandatory in this regard.


Commissioner/Secretary/Finance Officer
Chandernagore Municipal Corporation

Secretary

Chandannagar Municipal
Corporation

No.IA/Tend/2025-26/227/1 (12)

Date: 28.11.2025

Copy to :-

1. Mayor
2. Dy Mayor
3. MMIC (Street Light / Education / Trade Licence / Health / W.W / Sports / Store & Garage)
4. Commissioner/Secretary/Finance Officer
5. Engineer
6. A. O.
7. SAE (Elect)
8. S.A.-1 Please publish in Office Website.
9. Rabindra Bhavan
10. Office Notice Board


Commissioner/Secretary/Finance Officer
Chandernagore Municipal Corporation

Secretary

Chandannagar Municipal
Corporation

CHANDERNAGORE MUNICIPAL CORPORATION

ESTIMATE


APAS

Estimated Cost:- Rs. 5,974/-


Date of Completion: 7 days

Name of the work :- Installation of bright LED light on electric pole beside of house of Naren Bairagi at Surighat area under APAS Scheme -- Booth 52 sl no 09 ward no 06

Sl. No	Description of Work	Qty	Unit	Rate in Rs.	Amount
1	Supply and delivery of 45 watt LED Street Light with pressure die cast aluminium housing, IP66 protection, road way luminaire with high power LED as per the detail technical proposal specification & vendor list attached [Make-Crompton /Philips/Havells Warranty Period- 7 Years] Ref: Rate Redrive	1	No.	3579.46	3579.46
2	Fixing outdoor type fluorescent/SV/MV light fitting on pole including S&F 40 mm dia x 1.68 mts. long GI Pipe (ISI-Medium) bracket with 40 mmx10 mm thick, MS clamp etc. and providing wiring with 2x1/1.40 PVC insulated and sheathed wire (single core) from loop box at the base of pole to light fitting through pole & bracket (without control switch) including making connections & painting Ref: PWD(Electrical) Schedule 2017, H-5,H(4)	1	No.	1335.00	1335.00
Sub Total				RS	4,914.46
Add (@18%) Gst				RS	884.60
Sub Total				RS	5,799.06
Add (@1%) Cess				RS	57.99
Total				Rs	5,857.05
Add (@2%) Contingency				RS	117.14
Total				Rs	5,974.19


21.11.2025
SAE (ELECTRICAL)

CHANDERNAGORE MUNICIPAL CORPORATION


21/11/25
AE (MECHANICAL)
CHANDERNAGORE MUNICIPAL CORPORATION


21/11/25
COMMISSIONER
CHANDERNAGORE MUNICIPAL CORPORATION


MAYOR
CHANDERNAGORE MUNICIPAL CORPORATION

APAS


CHANDERNAGORE MUNICIPAL CORPORATION
ESTIMATE

Estimated Cost:- Rs. 8,545/-

Date of Completion: 7 days


Name of the work :- Construction of guardwall, arrangement of light & renovation of drain adjacent to pond in front of the house of Ashu Das at Jadughosh Lane Under
APAS Scheme -- Booth 40 sl no:-4 ward 04

SL No	Description of Work	Qty	Unit	Rate in Rs.	Amount
1	Supply and delivery of 30 watt LED Street Light with pressure die cast aluminium housing, IP66 protection, road way luminarie with high power LED as per the detail technical proposal specification & vendor list attached Make-Crompton /Philips/Havells Warranty Period- 7 Years Ref: Rate Redrive	2	Nos	2179.46	4358.92
2	Fixing outdoor type fluorescent/SV/MV light fitting on pole including S&F 40 mm dia x 1.68 mts. long GI Pipe (ISI-Medium) bracket with 40 mmx10 mm thick, MS clamp etc. and providing wiring with 2x1/1.40 PVC insulated and sheathed wire (single core) from loop box at the base of pole to light fitting through pole & bracket (without control switch) including making Ref: PWD(Electrical) Schedule 2017, H-5,H(4)	2	Nos	1335.00	2670.00
Sub Total				RS	7,028.92
Add (@18%) Gst				RS	1,265.21
Sub Total				RS	8,294.13
Add (@1%) Cess				RS	82.94
Total				Rs	8,377.07
Add (@2%) Contingency				RS	167.54
Total				Rs	8,544.61


21.11.2025

SAE (ELECTRICAL)

CHANDERNAGORE MUNICIPAL CORPORATION


21/11/25

AE (MECHANICAL)

CHANDERNAGORE MUNICIPAL CORPORATION


21/11/25

COMMISSIONER

CHANDERNAGORE MUNICIPAL CORPORATION


MAYOR

CHANDERNAGORE MUNICIPAL CORPORATION

CHANDERNAGORE MUNICIPAL CORPORATION

ESTIMATE

Estimated Cost:- Rs. 9,474/-

Date of Completion: 7 days

Name of the work :- Construction of Boundary Fencing in front of Student's Club with installation of bright light at Jadu Ghosh Lane Under
APAS Scheme -- Booth 40 sl no:-3 ward 04

SL No	Description of Work	Qty	Unit	Rate in Rs.	Amount
1	Supply and delivery of 90 watt LED Street Light with pressure die cast aluminium housing, IP66 protection, road way luminarie with high power LED as per the detail technical proposal specification & vendor list attached [Make-Crompton /Philips/Havells Warranty Period- 7 Years]	1	No.	6458.04	6458.04
	Ref: Rate Redrive				
2	Fixing outdoor type fluorescent/SV/MV light fitting on pole including S&F 40 mm dia x 1.68 mts. long GI Pipe (ISI-Medium) bracket with 40 mmx10 mm thick, MS clamp etc. and providing wiring with 2x1/1.40 PVC insulated and sheathed wire (single core) from loop box at the base of pole to light fitting through pole & bracket (without control switch) including making connections & painting	1	No.	1335.00	1335.00
	Ref: PWD(Electrical) Schedule 2017, H-5,H(4)				
	Sub Total			RS	7,793.04
	Add (@18%) Gst			RS	1,402.75
	Sub Total			RS	9,195.79
	Add (@1%) Cess			RS	91.96
	Total			Rs	9,287.75
	Add (@2%) Contingency			RS	185.75
	Total			Rs	9,473.50


21/11/25
SAE (ELECTRICAL)

CHANDERNAGORE MUNICIPAL CORPORATION


21/11/25
AE (MECHANICAL)
CHANDERNAGORE MUNICIPAL CORPORATION


21/11/25
COMMISSIONER
CHANDERNAGORE MUNICIPAL CORPORATION


MAYOR
CHANDERNAGORE MUNICIPAL CORPORATION

CHANDERNAGORE MUNICIPAL CORPORATION

ESTIMATE

APAS

Estimated Cost:- Rs. 5,974/-

Date of Completion: 7 days

Name of the work :- Installation of bright LED light in front house of Panchanan Dey at Kalachand Colony Under
APAS Scheme – Booth 34 sl no:-5 ward 01

SL No	Description of Work	Qty	Unit	Rate in Rs.	Amount
1	Supply and delivery of 45 watt LED Street Light with pressure die cast aluminium housing, IP66 protection, road way luminarie with high power LED as per the detail technical proposal specification & vendor list attached [Make-Crompton /Philips/Havells Warranty Period- 7 Years]	1	No.	3579.46	3579.46
	Ref: Rate Redrive				
2	Fixing outdoor type fluorescent/SV/MV light fitting on pole including S&F 40 mm dia x 1.68 mts. long GI Pipe (ISI-Medium) bracket with 40 mmx10 mm thick, MS clamp etc. and providing wiring with 2x1/1.40 PVC insulated and sheathed wire (single core) from loop box at the base of pole to light fitting through pole & bracket (without control switch) including making connections & painting	1	No.	1335.00	1335.00
	Ref: PWD(Electrical) Schedule 2017, H-5,H(4)				
Sub Total				RS	4,914.46
Add (@18%) Gst				RS	884.60
Sub Total				RS	5,799.06
Add (@1%) Cess				RS	57.99
Total				Rs	5,857.05
Add (@2%) Contingency				RS	117.14
Total				Rs	5,974.19

[Signature]
21.11.2025

SAE (ELECTRICAL)

CHANDERNAGORE MUNICIPAL CORPORATION

[Signature]
21/11/25

AE (MECHANICAL)

CHANDERNAGORE MUNICIPAL CORPORATION

[Signature]
21/11/25

COMMISSIONER

CHANDERNAGORE MUNICIPAL CORPORATION

[Signature]

MAYOR

CHANDERNAGORE MUNICIPAL CORPORATION

APAS

CHANDERNAGORE MUNICIPAL CORPORATION
ESTIMATE

Estimated Cost:- Rs. 5,974/-

Date of Completion: 7 days

Name of the work :- Installation of bright LED light on electric pole in front house of Gopal Karmakar at Guinbagan Area Under APAS Scheme -- Booth 34 sl no:-4 ward 01

SL No	Description of Work	Qty	Unit	Rate in Rs.	Amount
1	Supply and delivery of 45 watt LED Street Light with pressure die cast aluminium housing, IP66 protection, road way luminarie with high power LED as per the detail technical proposal specification & vendor list attached [Make-Crompton /Philips/Havells Warranty Period- 7 Years]	1	No.	3579.46	3579.46
	Ref: Rate Redrive				
2	Fixing outdoor type fluorescent/SV/MV light fitting on pole including S&F 40 mm dia x 1.68 mts. long GI Pipe (ISI-Medium) bracket with 40 mmx10 mm thick, MS clamp etc. and providing wiring with 2x1/1.40 PVC insulated and sheathed wire (single core) from loop box at the base of pole to light fitting through pole & bracket (without control switch) including making connections & painting	1	No.	1335.00	1335.00
	Ref: PWD(Electrical) Schedule 2017, H-5,H(4)				
	Sub Total			RS	4,914.46
	Add (@18%) Gst			RS	884.60
	Sub Total			RS	5,799.06
	Add (@1%) Cess			RS	57.99
	Total			RS	5,857.05
	Add (@2%) Contingency			RS	117.14
	Total			RS	5,974.19

S. P. S.
21/11/2025
SAE (ELECTRICAL)

CHANDERNAGORE MUNICIPAL CORPORATION

G. Karmakar
21/11/25
AE (MECHANICAL)

CHANDERNAGORE MUNICIPAL CORPORATION

S. P. S.
21/11/25
COMMISSIONER

CHANDERNAGORE MUNICIPAL CORPORATION

G. Karmakar
MAYOR
CHANDERNAGORE MUNICIPAL CORPORATION

CHANDERNAGORE MUNICIPAL CORPORATION

ESTIMATE


APAS

Estimated Cost:- Rs. 5,974/-

Date of Completion: 7 days

Name of the work :- Enhancement of illumination in front house of Sk Salim at Surerpukur Muslimpara Under APAS Scheme – Booth 34 sl no:-3 ward 01

SL No	Description of Work	Qty	Unit	Rate in Rs.	Amount
1	Supply and delivery of 45 watt LED Street Light with pressure die cast aluminium housing, IP66 protection, road way luminarie with high power LED as per the detail technical proposal specification & vendor list attached Make-Crompton /Philips/Havells Warranty Period- 7 Years	1	No.	3579.46	3579.46
	Ref: Rate Redrive				
2	Fixing outdoor type fluorescent/SV/MV light fitting on pole including S&F 40 mm dia x 1.68 mts. long GI Pipe (ISI-Medium) bracket with 40 mmx10 mm thick, MS clamp etc. and providing wiring with 2x1/1.40 PVC insulated and sheathed wire (single core) from loop box at the base of pole to light fitting through pole & bracket (without control switch) including making connections & painting	1	No.	1335.00	1335.00
	Ref: PWD(Electrical) Schedule 2017, H-5,H(4)				
	Sub Total			RS	4,914.46
	Add (@18%) Gst			RS	884.60
	Sub Total			RS	5,799.06
	Add (@1%) Cess			RS	57.99
	Total			Rs	5,857.05
	Add (@2%) Contingency			RS	117.14
	Total			Rs	5,974.19


21.11.2025

SAE (ELECTRICAL)

CHANDERNAGORE MUNICIPAL CORPORATION


21/11/25

AE (MECHANICAL)

CHANDERNAGORE MUNICIPAL CORPORATION


21/11/25

COMMISSIONER

CHANDERNAGORE MUNICIPAL CORPORATION



MAYOR

CHANDERNAGORE MUNICIPAL CORPORATION

CHANDERNAGORE MUNICIPAL CORPORATION

ESTIMATE

APAS

Estimated Cost:- Rs.26,895/-

Date of Completion: 10 days

Name of the work :- Installation of electric pole with bright LED light in front of Sri Nanda Bairagi at Bishaharitala
Bye Lane under
APAS Scheme – Booth 33 sl no 10 ward no 01

SL No	Description of Work	Qty	Unit	Rate in Rs.	Amount
1	Supplying of Swaged Steel Tubular pole (IS 2713, Pt. II 1980) for following designation and of following dimensions ---- 410-SP-1; 7.0 mtrs: 62.00Kg	1	No.	5383	5383
	Ref: UDMA(E/M) (Vol 1) Schedule 2018, page-3,1 (d)				
2	Erection of Single Steel tubular pole of length as given below with/without sole plate & Cap etc. in CC foundation (Proportion and dimension indicated below), having 600x600x150 mm thick CC (4:2:1) base block below sole plate/pole with hard jhama metal including CC (6:3:1) muffing 0.30 mts. dia and 0.30 mts. above ground level including 3 mm thick neat cemented finish and GI earth bolt after making drilled holes etc. on pole & carriage of pole upto 1.6 Km from Store to work-site including filling up the excavated earth pit with shifted soil and ramming properly ---- Upto 9.0 mtr. Size 0.6x0.6x1.70 mts	1	No.	2835.00	2835.00
	Ref: PWD(Electrical) Schedule 2017, H-1, (A)1(a)				
3	Extra on items 1& 2 above, for providing CC (6:3:1) base block (around the pole) dimension 0.45x0.45x0.60 mt. above ground level, neatly cemented finish (3 mm thick), at the base pole (in lieu of CC muffing) suitable for alkathene/ polythene pipe entry as directed for street light wiring, incl. S & F 20cmx15cmx10cm GI Loop box, 16SWG & incl. drilled hole in pole	1	No.	740.00	740.00
	Ref: PWD(Electrical) Schedule 2017, H-1, (A)3(a)(ii)				
4	Painting of Steel Tubular Pole of lengths and no. of coats of paint, as given below with ready mixed paint/primer of approved make, and brand incl. preparation of surface by sand paper/emery paper, cleaning etc. for receiving fresh coat of paint ---- (a) Upto 9.0 mtr. long pole -- (i)1st coat of aluminium paint over 1 coat of RO priming (ii)2nd coat of aluminium paint over 1st coat	1	No.	329.00	329.00
	Ref: PWD(Electrical) Schedule 2017, H-2, (A)4(a)				
5	Supplying of 1.1 KV. Grade PVC insulated Conductor of following cables (make: Polycab/ Gloster/Havells): 2 core 4sqmm	47	Mtr	73.00	3431.00
	Ref: UDMA(E/M) Schedule 2018, page-11, 1(a)1)				
6	Laying of cable upto 2 core 25 sqmm on wall/surface incl. S & F MS saddles with earthing attachment in 10 SWG GI (Hot Dip) Wire, making holes etc. as necy. mending good damages and painting ----	47	Mtr	57.00	2679.00
	Ref: PWD(Electrical) Schedule 2017, F-1, 2(a)				

7	Supply and delivery of 45 watt LED Street Light with pressure die cast aluminium housing, IP66 protection, road way luminarie with high power LED as per the detail technical proposal specification & vendor list attached [Make-Crompton /Philips / Havells) Warranty Period- 7 Years]	1	No.	3579.46	3579.46
	Ref: Rate Redrive				
8	Fixing outdoor type fluorescent/SV/MV light fitting on pole including S&F 40 mm dia x 1.68 mts. long GI Pipe (ISI-Medium) bracket with 40 mmx10 mm thick, MS clamp etc. and providing wiring with 2x1/1.40 PVC insulated and sheathed wire (single core) from loop box at the base of pole to light fitting through pole & bracket (without control switch) including making connections & painting	1	No.	1335.00	1335.00
	Ref: PWD(Electrical) Schedule 2017, H-5,H(4)				
9	Supplying and fixing 240/415 V MCB of Breaking capacity 10 KA & C characteristics on din rail of existing DBs and necessary connection --- 6-32 A SPN (Standard)	1	No.	444.00	444.00
	Ref: PWD(Electrical) Schedule 2017, D-7/8				
10	Earthing with 50mm dia GI pipe 3.64mm thick x 3.04mtrs long and 1x4SWG GI (Hot Dip) wire (4mtrs long), 13mm dia x 80mm long GI bolts, double nuts, double washers incl. S&F 15mm dia GI pipe protection (1mtr long) to be filled with bitumen partly under the ground level and partly above ground level driven to an average depth of 3.65mts below the ground level as below: by ISI-Medium GI pipe	1	No.	1369.00	1369.00
	Ref:PWD Schedule (Electrical)2017, Page-G-1/ 2(a)				
	Sub Total		RS		22,124.46
	Add (@18%) Gst		RS		3,982.40
	Sub Total		RS		26,106.86
	Add (@1%) Cess		RS		261.07
	Total		Rs		26,367.93
	Add (@2%) Contingency		RS		527.36
	Total		Rs		26,895.29
	Say		Rs		26,895


 21-11-2025
 SAE (ELECTRICAL)
 CHANDERNAGORE MUNICIPAL CORPORATION


 21/11/25
 AE (MECHANICAL)
 CHANDERNAGORE MUNICIPAL CORPORATION


 21/11/25
 COMMISSIONER
 CHANDERNAGORE MUNICIPAL CORPORATION


 MAYOR
 CHANDERNAGORE MUNICIPAL CORPORATION

CHANDERNAGORE MUNICIPAL CORPORATION

ESTIMATE

APAS

Estimated Cost:- Rs. ~~18,000/-~~ 17,923/-


Date of Completion: 7 days

Name of the work :- Enhancement of illumination in front house of Sri Shibu Bhowmik, Riju Mondal, and Aviraj Mukherjee at Bishaharitala Purbapara Area under APAS Scheme -- Booth 33 sl no 05 ward no 01

SL.No	Description of Work	Qty	Unit	Rate in Rs.	Amount
1	Supply and delivery of 45 watt LED Street Light with pressure die cast aluminium housing, IP66 protection, road way luminarie with high power LED as per the detail technical proposal specification & vendor list attached Make-Crompton /Philips/Havells Warranty Period- 7 Years] Ref: Rate Redrive	3	Nos	3579.46	10738.38
2	Fixing outdoor type fluorescent/SV/MV light fitting on pole including S&F 40 mm dia x 1.68 mts. long GI Pipe (ISI-Medium) bracket with 40 mmx10 mm thick, MS clamp etc. and providing wiring with 2x1/1.40 PVC insulated and sheathed wire (single core) from loop box at the base of pole to light fitting through pole & bracket (without control switch) including making connections & painting Ref: PWD(Electrical) Schedule 2017, H-5,H(4)	3	Nos	1335.00	4005.00
	Sub Total			RS	14,743.38
	Add (@18%) Gst			RS	2,653.81
	Sub Total			RS	17,397.19
	Add (@1%) Cess			RS	173.97
	Total			Rs	17,571.16
	Add (@2%) Contingency			RS	351.42
	Total			Rs	17,922.58


21.11.2025
SAE (ELECTRICAL)

CHANDERNAGORE MUNICIPAL CORPORATION


21/11/25
AE (MECHANICAL)
CHANDERNAGORE MUNICIPAL CORPORATION


21/11/25
COMMISSIONER
CHANDERNAGORE MUNICIPAL CORPORATION


MAYOR
CHANDERNAGORE MUNICIPAL CORPORATION

CHANDERNAGORE MUNICIPAL CORPORATION

ESTIMATE

APAS

Estimated Cost:- Rs. 4,272/-

Date of Completion: 7 days

Name of the work :- Arrangement of Bright LED Light in front house of Pathak at Dr. Gali, Kantapur
under
APAS Scheme -- Booth 28 sl no 06 ward no 02

SL No	Description of Work	Qty	Unit	Rate in Rs.	Amount
1	Supply and delivery of 30 watt LED Street Light with pressure die cast aluminium housing, IP66 protection, road way luminaire with high power LED as per the detail technical proposal specification & vendor list attached [Make-Crompton /Philips/Havells Warranty Period- 7 Years]	1	No.	2179.46	2179.46
	Ref: Rate Redrive				
2	Fixing outdoor type fluorescent/SV/MV light fitting on pole including S&F 40 mm dia x 1.68 mts. long GI Pipe (ISI-Medium) bracket with 40 mmx10 mm thick, MS clamp etc. and providing wiring with 2x1/1.40 PVC insulated and sheathed wire (single core) from loop box at the base of pole to light fitting through pole & bracket (without control switch) including making connections & painting	1	No.	1335.00	1335.00
	Ref: PWD(Electrical) Schedule 2017, H-5,H(4)				
	Sub Total			RS	3,514.46
	Add (@18%) Gst			RS	632.60
	Sub Total			RS	4,147.06
	Add (@1%) Cess			RS	41.47
	Total			Rs	4,188.53
	Add (@2%) Contingency			RS	83.77
	Total			Rs	4,272.30


21.11.2025
SAE (ELECTRICAL)

CHANDERNAGORE MUNICIPAL CORPORATION


21/11/25
AE (MECHANICAL)
CHANDERNAGORE MUNICIPAL CORPORATION


21/11/25

COMMISSIONER
CHANDERNAGORE MUNICIPAL CORPORATION


MAYOR
CHANDERNAGORE MUNICIPAL CORPORATION

CHANDERNAGORE MUNICIPAL CORPORATION

ESTIMATE


APAS

Estimated Cost:- Rs. 5,974/-

Date of Completion: 7 days

Name of the work :- Installation of bright LED light in front house of Satish Pal at Haridradanga Under
APAS Scheme -- Booth 25 sl no:-5 ward 01

SL No	Description of Work	Qty	Unit	Rate in Rs.	Amount
1	Supply and delivery of 45 watt LED Street Light with pressure die cast aluminium housing, IP66 protection, road way luminarie with high power LED as per the detail technical proposal specification & vendor list attached Make-Crompton /Philips/Havells Warranty Period- 7 Years Ref: Rate Redrive	1	No.	3579.46	3579.46
2	Fixing outdoor type fluorescent/SV/MV light fitting on pole including S&F 40 mm dia x 1.68 mts. long GI Pipe (ISI-Medium) bracket with 40 mmx10 mm thick, MS clamp etc. and providing wiring with 2x1/1.40 PVC insulated and sheathed wire (single core) from loop box at the base of pole to light fitting through pole & bracket (without control switch) including making connections & painting Ref: PWD(Electrical) Schedule 2017, H-5,H(4)	1	No.	1335.00	1335.00
Sub Total				RS	4,914.46
Add (@18%) Gst				RS	884.60
Sub Total				RS	5,799.06
Add (@1%) Cess				RS	57.99
Total				Rs	5,857.05
Add (@2%) Contingency				RS	117.14
Total				Rs	5,974.19


21-11-2025
SAE (ELECTRICAL)

CHANDERNAGORE MUNICIPAL CORPORATION


21/11/25
AE (MECHANICAL)

CHANDERNAGORE MUNICIPAL
CORPORATION


21/11/25

COMMISSIONER
CHANDERNAGORE MUNICIPAL CORPORATION


MAYOR

CHANDERNAGORE MUNICIPAL
CORPORATION