



CHANDERNAGORE MUNICIPAL CORPORATION

No.IA/Tend/2025-26/187A

Dated. 07.11.2025

URGENT NOTICE INVITING QUOTATION:

APAS Fund

Sealed tenders are invited from the experienced, resourceful and interested Vendors/Suppliers/Contractors to complete the work of the following items required for Electric Dept. under the control of this Corporation individually or unanimously. Vendors/Suppliers/Contractors may participate for both individually or unanimously of the following works.


Quotations are to be given on or before 14.11.2025 within 3 p.m. and will be opened on the same day at 3.30 p.m. Rates should be inclusive of all the taxes and other incidental charges if any. In case of accepted tenderers whose rates have been accepted, fails to supply the required items within the stipulated date & time, necessary items will be purchased from the available sources and the difference in cost will be recovered from the tenderers. The Corporation reserves the right to accept or reject any tender without assigning any reason whatsoever.

Sl. No.	Description of the Items	Booth No.	Sl. No.	Ward No.	Quantity Required	Rate Required
1.	Installation of new Electric light with bright LED Light in front house of Moni Khatub at Chalke Para Bye Lane.	119	12	17	One Job	Entire Work

Laying of cable upto 2 cmt 22 sqmm on wall surface incl. 8 A.P. 118 cables with routing attachment to 10 SWG GI (Hot Dip) Wire, making holes etc. as may be required good damages and painting ---

Encl: Estimate of All Works.

PAN, GST and Copy of Trade Enlistment Certificate are Mandatory in this regard.



Commissioner/Secretary/Finance Officer
Chandernagore Municipal Corporation

No.IA/Tend/2025-26/187/A/1 (12)

Dated. 07.11.2025

Copy to :-

1. Mayor
2. Dy Mayor
3. MMIC (Street Light / Education / Trade Licence / Health / W.W / Sports / Store & Garage)
4. Commissioner/Secretary/Finance Officer
5. Engineer
6. A. O.
7. SAE (Elect)
8. S.A.-1 Please publish in Office Website.
9. Rabindra Bhabar
10. Office Notice Board


Commissioner/Secretary/Finance Officer
Chandernagore Municipal Corporation

CHANDERNAGORE MUNICIPAL CORPORATION

ESTIMATE

Estimated Cost:- Rs.32,435/-

Date of Completion: 7 days

Name of the work :- Installation of new electric pole with bright LED Light in front house of Moni Khatun at Chalke Para Bye Lane under APAS Scheme -- Booth 119 sl no 12 w 17

SL No	Description of Work	Qty	Unit	Rate in Rs.	Amount
1	Supplying of Swaged Steel Tubular pole (IS 2713, Pt. II 1980) for following designation and of following dimensions ---- 410-SP-9 ; 7.5mtrs: 110Kg	1	No.	9550	9550
	Ref: UDMA(E/M) (Vol 1) Schedule 2018, page-3,1 (e)				
2	Erection of Single Steel tubular pole of length as given below with/without sole plate & Cap etc. in CC foundation (Proportion and dimension indicated below), having 600x600x150 mm thick CC (4:2:1) base block below sole plate/pole with hard jhama metal including CC (6:3:1) muffing 0.30 mts. dia and 0.30 mts. above ground level including 3 mm thick neat cemented finish and GI earth bolt after making drilled holes etc. on pole & carriage of pole upto 1.6 Km from Store to work-site including filling up the excavated earth pit with shifted soil and ramming properly ---- Upto 9.0 mtr. Size 0.6x0.6x1.70 mts	1	No.	2835.00	2835.00
	Ref: PWD(Electrical) Schedule 2017, H-1, (A)1(a)				
3	Extra on items 1 & 2 above, for providing CC (6:3:1) base block (around the pole) dimension 0.45x0.45x0.60 mt. above ground level, neatly cemented finish (3 mm thick), at the base pole (in lieu of CC muffing) suitable for alkathene/polythene pipe entry as directed for street light wiring, incl. S & F 20cmx15cmx10cm GI Loop box, 16SWG & incl. drilled hole in pole	1	Nos	740.00	740.00
	Ref: PWD(Electrical) Schedule 2017, H-1, (A)3(a)(ii)				
4	Painting of Steel Tubular Pole of lengths and no. of coats of paint, as given below with ready mixed paint/primer of approved make, and brand incl. preparation of surface by sand paper/emery paper, cleaning etc. for receiving fresh coat of paint ---- (a) Upto 9.0 mtr. long pole -- (i)1st coat of aluminium paint over 1 coat of RO priming (ii)2nd coat of aluminium paint over 1st coat	1	No.	329.00	329.00
	Ref: PWD(Electrical) Schedule 2017, H-2, (A)4(a)				
5	Supplying of 1.1 KV. Grade PVC insulated Conductor of following cables (make: Polycab/Gloster/Havells): 2 core 4sqmm	50	Mtr	73.00	3650.00
	Ref: UDMA(E/M) Schedule 2018, page-13, 1(a)1				
6	Laying of cable upto 2 core 25 sqmm on wall/surface incl. S & F MS saddles with earthing attachment in 10 SWG GI (Hot Dip) Wire, making holes etc. as necy. mending good damages and painting ----	50	Mtr	57.00	2850.00

--	--

1	No.	3579.46
---	-----	---------

1	No.	1335.00
---	-----	---------

1000

1	No.	444.00
---	-----	--------

1	No.	1369.00
---	-----	---------

RS

RS

RS

RS

R5

R5

Free