



CHANDERNAGORE MUNICIPAL CORPORATION

No.IA/Tend/2025-26/245

Dated. 29.11.2025

URGENT NOTICE INVITING QUOTATION:

Fund: APAS.

Sealed tenders are invited from the experienced, resourceful and interested Vendors/Suppliers/Contractors to complete the work of the following items required for Electric Dept. under the control of this Corporation individually or unanimously. Vendors/Supplier/Contractors may participate for both individually or unanimously of the following works.

Quotations are to be given on or before 08.12.2025 within 3 p.m. and will be opened on the same day at 3.30 p.m. Rates should be inclusive of all the taxes and other incidental charges if any. In case of accepted tenderers whose rates have been accepted, fails to supply the required items within the stipulated date & time, necessary items will be purchased from the available sources and the difference in cost will be recovered from the tenderers. The Corporation reserves the right to accept or reject any tender without assigning any reason whatsoever.

Sl. No.	Description of the Items	Booth No	Sl. No.	Ward No.	Quantity Required	Rate Required
1.	Enhancement of illumination (Wattage) in front of the house of Biswajit Das at KBC Road.	114	04	16	One Job	Entire Work
2.	Enhancement of illumination (Wattage) beside Goli of the house of R.N. Ghosh at Hatkhola.	114	01	16	One Job	Entire Work
3.	Arrangement of new light beside Sener Eagan Aikyatan Club.	112	03	16	One Job	Entire Work
4.	Enhancement of illumination (Wattage) in front of house of Pradip Ghosh at Ashatosh Neogy Bye Lane.	111	06	16	One Job	Entire Work
5.	Enhancement of illumination (Wattage) in front of house of Pratip Konar at Ashatosh Niyogy Bye Lane.	111	05	16	One Job	Entire Work
6.	Installation of light in front of house of Tapan Nandy at Sipra Mukherjee's Lane.	99	17	12	One Job	Entire Work
7.	Installation of light in front of house of Tapan Nandy at Sipra Mukherjee's Lane.	99	17	12	One Job	Entire Work
8.	Installation of light in front of Ispat Sangha.	99	12	12	One Job	Entire Work
9.	Installation of light required for new light post near collage Goli.	98	15	12	One Job	Entire Work
10.	Installation of light required for new light post near Barabazar Thana Goli.	98	14	12	One Job	Entire Work
11.	Installation of light required for new light post in front of Joraki Cinema Hall.	98	13	12	One Job	Entire Work
12.	Installation of light required for new light post near Barabazar Jagadhatri Goli.	98	12	12	One Job	Entire Work
13.	Installation of light required in front of Saradi Apartment near Barabazar Mishra Lane.	98	05	12	One Job	Entire Work

Encl: Estimate of all Works are attached here-with.

PAN, GST and Copy of Trade Enlistment Certificate are Mandatory in this regard.

Ans 29/11/25
Commissioner/Secretary/Finance Officer
Chandernagore Municipal Corporation

No.IA/Tend/2025-26/245/1 (12)

Date: 29.11.2025

Copy to :-

1. Mayor
2. Dy Mayor
3. MMIC (Street Light / Education / Trade Licence / Health / W.W / Sports / Store & Garage)
4. Commissioner/Secretary/Finance Officer
5. Engineer
6. A. O.
7. SAE (Elect)
8. S.A.-I Please publish in Office Website.
9. Rabindra Bhaban
10. Office Notice Board



Ans 29/11/25
Commissioner/Secretary/Finance Officer
Chandernagore Municipal Corporation

CHANDERNAGORE MUNICIPAL CORPORATION
ESTIMATE

APAS

Estimated Cost:- Rs.5,974/-

Date of Completion: 7 days

Name of the work :- Enhancement of illumination(wattage) in front of the house of Biswajit Das at K.B.C. Road
Under
APAS Scheme – Booth 114_sl no 04_w 16

SL No	Description of Work	Qty	Unit	Rate in Rs.	Amount
1	Supply and delivery of 45 watt LED Street Light with pressure die cast aluminium housing, IP66 protection, road way luminarie with high power LED as per the detail technical proposal specification & vendor list attached Make-Crompton /Philips Havells Warranty Period- 7 Years	1	No.	3579.46	3579.46
	Ref: Rate Redrive				
2	Fixing outdoor type fluorescent/SV/MV light fitting on pole including S&F 40 mm dia x 1.68 mts. long GI Pipe (ISI-Medium) bracket with 40 mmx10 mm thick, MS clamp etc. and providing wiring with 2x1/1.40 PVC insulated and sheathed wire (single core) from loop box at the base of pole to light fitting through pole & bracket (without control switch) including making connections & painting	1	No.	1335.00	1335.00
	Ref: PWD(Electrical) Schedule 2017, H-5,H(4)				
	Sub Total			RS	4,914.46
	Add (@18%) Gst			RS	884.60
	Sub Total			RS	5,799.06
	Add (@1%) Cess			RS	57.99
	Total			Rs	5,857.05
	Add (@2%) Contingency			RS	117.14
	Total			Rs	5,974.19

[Signature]
17/11/2025
SAE (ELECTRICAL)

CHANDERNAGORE MUNICIPAL CORPORATION

[Signature]
17/11/25
AE (MECHANICAL)

CHANDERNAGORE MUNICIPAL CORPORATION

[Signature]

COMMISSIONER
CHANDERNAGORE MUNICIPAL CORPORATION

[Signature]

MAYOR
CHANDERNAGORE MUNICIPAL CORPORATION

CHANDERNAGORE MUNICIPAL CORPORATION
ESTIMATE

APAS

Estimated Cost:- Rs.4,272/-

Date of Completion: 7 days

Name of the work :- Enhancement of illumination(wattage) beside goli of the house of R.N.Ghosh at Hatkhola Under APAS Scheme -- Booth 114_sl no 01_w 16

SL No	Description of Work	Qty	Unit	Rate in Rs.	Amount
1	Supply and delivery of 30 watt LED Street Light with pressure die cast aluminium housing, IP66 protection, road way luminarie with high power LED as per the detail technical proposal specification & vendor list attached Make-Crompton /Philips Havells Warranty Period- 7 Years Ref: Rate Redrive	1	No.	2179.46	2179.46
2	Fixing outdoor type fluorescent/SV/MV light fitting on pole including S&F 40 mm dia x 1.68 mts. long GI Pipe (ISI-Medium) bracket with 40 mmx10 mm thick, MS clamp etc. and providing wiring with 2x1/1.40 PVC insulated and sheathed wire (single core) from loop box at the base of pole to light fitting through pole & bracket (without control switch) including making connections & painting Ref: PWD(Electrical) Schedule 2017, H-5,H(4)	1	No.	1335.00	1335.00
Sub Total				RS	3,514.46
Add (@18%) Gst				RS	632.60
Sub Total				RS	4,147.06
Add (@1%) Cess				RS	41.47
Total				Rs	4,188.53
Add (@2%) Contingency				RS	83.77
Total				Rs	4,272.30

17.11.2025
SAE (ELECTRICAL)

CHANDERNAGORE MUNICIPAL CORPORATION

17/11/25
AE (MECHANICAL)

CHANDERNAGORE MUNICIPAL CORPORATION

A

COMMISSIONER
CHANDERNAGORE MUNICIPAL CORPORATION

[Signature]

MAYOR
CHANDERNAGORE MUNICIPAL CORPORATION

CHANDERNAGORE MUNICIPAL CORPORATION
ESTIMATE


APAS

Estimated Cost:- Rs. 5,974/-

Date of Completion: 7 days

Name of the work :- Arrangement of new light beside Sener Bagan Aikyatan Club Under
APAS Scheme – Booth 112 sl no:-3 ward 16

SL No	Description of Work	Qty	Unit	Rate in Rs.	Amount
1	Supply and delivery of 45 watt LED Street Light with pressure die cast aluminium housing, IP66 protection, road way luminarie with high power LED as per the detail technical proposal specification & vendor list attached Make-Crompton /Philips/Havells Warranty Period- 7 Years Ref: Rate Redrive	1	No.	3579.46	3579.46
2	Fixing outdoor type fluorescent/SV/MV light fitting on pole including S&F 40 mm dia x 1.68 mts. long GI Pipe (ISI-Medium) bracket with 40 mmx10 mm thick, MS clamp etc. and providing wiring with 2x1/1.40 PVC insulated and sheathed wire (single core) from loop box at the base of pole to light fitting through pole & bracket (without control switch) including making connections & painting Ref: PWD(Electrical) Schedule 2017, H-5,H(4)	1	No.	1335.00	1335.00
	Sub Total			RS	4,914.46
	Add (@18%) Gst			RS	884.60
	Sub Total			RS	5,799.06
	Add (@1%) Cess			RS	57.99
	Total			Rs	5,857.05
	Add (@2%) Contingency			RS	117.14
	Total			Rs	5,974.19


17.11.2015

SAE (ELECTRICAL)

CHANDERNAGORE MUNICIPAL CORPORATION


17/11/25

AE (MECHANICAL)

CHANDERNAGORE MUNICIPAL CORPORATION



COMMISSIONER

CHANDERNAGORE MUNICIPAL CORPORATION



MAYOR

CHANDERNAGORE MUNICIPAL CORPORATION

CHANDERNAGORE MUNICIPAL CORPORATION

ESTIMATE

APAS

Estimated Cost:- Rs. 12,817/-

Date of Completion: 7 days

Name of the work :- Enhancement of illumination(wattage) in front of the house of Prdip Ghosh at
Ashutosh Niyogy Bye Lane Under
APAS Scheme -- Booth 111 sl no:-06 ward 16

SL.No	Description of Work	Qty	Unit	Rate in Rs.	Amount
1	Supply and delivery of 30 watt LED Street Light with pressure die cast aluminium housing, IP66 protection, road way luminarie with high power LED as per the detail technical proposal specification & vendor list attached Make-Crompton /Philips/Havells Warranty Period- 7 Years Ref: Rate Redrive	3	Nos	2179.46	6538.38
2	Fixing outdoor type fluorescent/SV/MV light fitting on pole including S&F 40 mm dia x 1.68 mts. long GI Pipe (ISI-Medium) bracket with 40 mmx10 mm thick, MS clamp etc. and providing wiring with 2x1/1.40 PVC insulated and sheathed wire (single core) from loop box at the base of pole to light fitting through pole & bracket (without control switch) including making connections & painting Ref: PWD(Electrical) Schedule 2017, H-5,H(4)	3	Nos	1335.00	4005.00
Sub Total				RS	10,543.38
Add (@18%) Gst				RS	1,897.81
Sub Total				RS	12,441.19
Add (@1%) Cess				RS	124.41
Total				Rs	12,565.60
Add (@2%) Contingency				RS	251.31
Total				Rs	12,816.91

[Signature]
17-11-2025
SAE (ELECTRICAL)

CHANDERNAGORE MUNICIPAL CORPORATION

[Signature]
17/11/25
AE (MECHANICAL)

CHANDERNAGORE MUNICIPAL CORPORATION

[Signature]

COMMISSIONER
CHANDERNAGORE MUNICIPAL CORPORATION

[Signature]

MAYOR
CHANDERNAGORE MUNICIPAL CORPORATION

CHANDERNAGORE MUNICIPAL CORPORATION

ESTIMATE

APAS

Estimated Cost:- Rs. 8,545/-

Date of Completion: 7 days

Name of the work :- Enhancement of illumination(wattage) in front of the house of Pratip Konar at Ashutosh Niyogy Bye Lane Under APAS Scheme - Booth 111 sl no:-05 ward 16

SL.No	Description of Work	Qty	Unit	Rate in Rs.	Amount
1	Supply and delivery of 30 watt LED Street Light with pressure die cast aluminium housing, IP66 protection, road way luminarie with high power LED as per the detail technical proposal specification & vendor list attached Make-Crompton /Philips/Havells Warranty Period- 7 Years Ref: Rate Redrive	2	Nos	2179.46	4358.92
2	Fixing outdoor type fluorescent/SV/MV light fitting on pole including S&F 40 mm dia x 1.68 mts. long GI Pipe (ISI-Medium) bracket with 40 mmx10 mm thick, MS clamp etc. and providing wiring with 2x1/1.40 PVC insulated and sheathed wire (single core) from loop box at the base of pole to light fitting through pole & bracket (without control switch) including making connections & painting Ref: PWD(Electrical) Schedule 2017, H-5,H(4)	2	Nos	1335.00	2670.00
Sub Total					
				RS	7,028.92
				Add (@18%) Gst	
				RS	1,265.21
				Sub Total	
				RS	8,294.13
				Add (@1%) Cess	
				RS	82.94
				Total	
				Rs	8,377.07
				Add (@2%) Contingency	
				RS	167.54
				Total	
				Rs	8,544.61

[Signature]
17.11.2025

SAE (ELECTRICAL)

CHANDERNAGORE MUNICIPAL CORPORATION

[Signature]
17/11/25

AE (MECHANICAL)

CHANDERNAGORE MUNICIPAL CORPORATION

[Signature]

COMMISSIONER

CHANDERNAGORE MUNICIPAL CORPORATION

[Signature]

MAYOR

CHANDERNAGORE MUNICIPAL CORPORATION

CHANDERNAGORE MUNICIPAL CORPORATION

ESTIMATE

APAS

Estimated Cost:- Rs. 4,272/-

Date of Completion: 7 days

Name of the work :- Installation of light in front of house of Tapan Nandy at Sipra Mukherjee's Lane
Under
APAS Scheme -- Booth 99 sl no:-17 ward 12

SL No	Description of Work	Qty	Unit	Rate in Rs.	Amount
1	Supply and delivery of 30 watt LED Street Light with pressure die cast aluminium housing, IP66 protection, road way luminarie with high power LED as per the detail technical proposal specification & vendor list attached [Make-Crompton /Philips/Havells Warranty Period- 7 Years Ref: Rate Redrive	1	No.	2179.46	2179.46
2	Fixing outdoor type fluorescent/SV/MV light fitting on pole including S&F 40 mm dia x 1.68 mts. long GI Pipe (ISI-Medium) bracket with 40 mmx10 mm thick, MS clamp etc. and providing wiring with 2x1/1.40 PVC insulated and sheathed wire (single core) from loop box at the base of pole to light fitting through pole & bracket (without control switch) including making connections & painting Ref: PWD(Electrical) Schedule 2017, H-5,H(4)	1	No.	1335.00	1335.00
Sub Total				RS	3,514.46
Add (@18%) Gst				RS	632.60
Sub Total				RS	4,147.06
Add (@1%) Cess				RS	41.47
Total				Rs	4,188.53
Add (@2%) Contingency				RS	83.77
Total				Rs	4,272.30

[Signature]
17.11.2025
SAE (ELECTRICAL)

CHANDERNAGORE MUNICIPAL CORPORATION

[Signature]
17/11/25
AE (MECHANICAL)

CHANDERNAGORE MUNICIPAL CORPORATION

[Signature]
COMMISSIONER
CHANDERNAGORE MUNICIPAL CORPORATION

[Signature]
MAYOR
CHANDERNAGORE MUNICIPAL CORPORATION

APAS

CHANDERNAGORE MUNICIPAL CORPORATION
ESTIMATE

Estimated Cost:- Rs. 4,272/-

Date of Completion: 7 days

Name of the work :- Installation of light in front of Ispat Sangha Under
APAS Scheme – Booth 99 sl no:-12 ward 12

SL No	Description of Work	Qty	Unit	Rate in Rs.	Amount
1	Supply and delivery of 30 watt LED Street Light with pressure die cast aluminium housing, IP66 protection, road way luminarie with high power LED as per the detail technical proposal specification & vendor list attached Make-Crompton /Philips/Havells Warranty Period- 7 Years Ref: Rate Redrive	1	Nos	2179.46	2179.46
2	Fixing outdoor type fluorescent/SV/MV light fitting on pole including S&F 40 mm dia x 1.68 mts. long GI Pipe (ISI-Medium) bracket with 40 mmx10 mm thick, MS clamp etc. and providing wiring with 2x1/1.40 PVC insulated and sheathed wire (single core) from loop box at the base of pole to light fitting through pole & bracket (without control switch) including making connections & painting Ref: PWD(Electrical) Schedule 2017, H-5,H(4)	1	Nos	1335.00	1335.00
Sub Total				RS	3,514.46
Add (@18%) Gst				RS	632.60
Sub Total				RS	4,147.06
Add (@1%) Cess				RS	41.47
Total				Rs	4,188.53
Add (@2%) Contingency				RS	83.77
Total				Rs	4,272.30

[Signature]
17-11-2025

SAE (ELECTRICAL)

CHANDERNAGORE MUNICIPAL CORPORATION

[Signature]
17/11/25

AE (MECHANICAL)
CHANDERNAGORE MUNICIPAL CORPORATION

[Signature]

COMMISSIONER
CHANDERNAGORE MUNICIPAL CORPORATION

[Signature]

MAYOR
CHANDERNAGORE MUNICIPAL CORPORATION

CHANDERNAGORE MUNICIPAL CORPORATION

ESTIMATE

APAS

Estimated Cost:- Rs. 8,545/-

Date of Completion: 7 days

Name of the work :- Installation of light required for new light post near College Goli Under APAS Scheme -- Booth 98 sl no:-15 ward 12

Sl. No	Description of Work	Qty	Unit	Rate in Rs.	Amount
1	Supply and delivery of 30 watt LED Street Light with pressure die cast aluminium housing, IP66 protection, road way luminarie with high power LED as per the detail technical proposal specification & vendor list attached Make-Crompton /Philips/Havells Warranty Period- 7 Years Ref: Rate Redrive	2	Nos	2179.46	4358.92
2	Fixing outdoor type fluorescent/SV/MV light fitting on pole including S&F 40 mm dia x 1.68 mts. long GI Pipe (ISI-Medium) bracket with 40 mmx10 mm thick, MS clamp etc. and providing wiring with 2x1/1.40 PVC insulated and sheathed wire (single core) from loop box at the base of pole to light fitting through pole & bracket (without control switch) including making connections & painting Ref: PWD(Electrical) Schedule 2017, H-5,H(4)	2	Nos	1335.00	2670.00
Sub Total				RS	7,028.92
Add (@18%) Gst				RS	1,265.21
Sub Total				RS	8,294.13
Add (@1%) Cess				RS	82.94
Total				Rs	8,377.07
Add (@2%) Contingency				RS	167.54
Total				Rs	8,544.61

[Signature]

17-11-2025

SAE (ELECTRICAL)

CHANDERNAGORE MUNICIPAL CORPORATION

[Signature]

17/11/25

AE (MECHANICAL)

CHANDERNAGORE MUNICIPAL CORPORATION

[Signature]

COMMISSIONER

CHANDERNAGORE MUNICIPAL CORPORATION

[Signature]

MAYOR

CHANDERNAGORE MUNICIPAL CORPORATION

CHANDERNAGORE MUNICIPAL CORPORATION

APAS

ESTIMATE

Estimated Cost:- Rs. 17,089/-

Date of Completion: 7 days

Name of the work :- Installation of light required for new light post near Barabazar Thana Goli Under
APAS Scheme -- Booth 98 sl no:-14 ward 12

SL No	Description of Work	Qty	Unit	Rate in Rs.	Amount
1	Supply and delivery of 30 watt LED Street Light with pressure die cast aluminium housing, IP66 protection, road way luminarie with high power LED as per the detail technical proposal specification & vendor list attached Make-Crompton /Philips/Havells Warranty Period- 7 Years Ref: Rate Redrive	4	Nos	2179.46	8717.84
2	Fixing outdoor type fluorescent/SV/MV light fitting on pole including S&F 40 mm dia x 1.68 mts. long GI Pipe (ISI-Medium) bracket with 40 mmx10 mm thick, MS clamp etc. and providing wiring with 2x1/1.40 PVC insulated and sheathed wire (single core) from loop box at the base of pole to light fitting through pole & bracket (without control switch) including making connections & painting Ref: PWD(Electrical) Schedule 2017, H-5,H(4)	4	Nos	1335.00	5340.00
Sub Total				RS	14,057.84
Add (@18%) Gst				RS	2,530.41
Sub Total				RS	16,588.25
Add (@1%) Cess				RS	165.88
Total				Rs	16,754.13
Add (@2%) Contingency				RS	335.08
Total				Rs	17,089.22


17-11-2025
SAE (ELECTRICAL)

CHANDERNAGORE MUNICIPAL CORPORATION


17/11/25
AE (MECHANICAL)

CHANDERNAGORE MUNICIPAL
CORPORATION



COMMISSIONER
CHANDERNAGORE MUNICIPAL CORPORATION



MAYOR
CHANDERNAGORE MUNICIPAL
CORPORATION

CHANDERNAGORE MUNICIPAL CORPORATION
ESTIMATE

APAS

Estimated Cost:- Rs. 9,474/-

Date of Completion: 7 days

Name of the work :- Installation of light required for new light post in front of Jonski Cinema Hall Under APAS Scheme -- Booth 98 sl no:-13 ward 12

SL No	Description of Work	Qty	Unit	Rate in Rs.	Amount
1	Supply and delivery of 90 watt LED Street Light with pressure die cast aluminium housing, IP66 protection, road way luminarie with high power LED as per the detail technical proposal specification & vendor list attached Make-Crompton /Philips/Havells Warranty Period- 7 Years Ref: Rate Redrive	1	No.	6458.04	6458.04
2	Fixing outdoor type fluorescent/SV/MV light fitting on pole including S&F 40 mm dia x 1.68 mts. long GI Pipe (ISI-Medium) bracket with 40 mmx10 mm thick, MS clamp etc. and providing wiring with 2x1/1.40 PVC insulated and sheathed wire (single core) from loop box at the base of pole to light fitting through pole & bracket (without control switch) including making connections & painting Ref: PWD(Electrical) Schedule 2017, H-5,H(4)	1	No.	1335.00	1335.00
Sub Total				RS	7,793.04
Add (@18%) Gst				RS	1,402.75
Sub Total				RS	9,195.79
Add (@1%) Cess				RS	91.96
Total				Rs	9,287.75
Add (@2%) Contingency				RS	185.75
Total				Rs	9,473.50

[Signature]

17/11/2025

SAE (ELECTRICAL)

CHANDERNAGORE MUNICIPAL CORPORATION

[Signature]
17/11/25

AE (MECHANICAL)

CHANDERNAGORE MUNICIPAL CORPORATION

[Signature]

COMMISSIONER

CHANDERNAGORE MUNICIPAL CORPORATION

[Signature]

MAYOR

CHANDERNAGORE MUNICIPAL CORPORATION

CHANDERNAGORE MUNICIPAL CORPORATION
ESTIMATE

APAS

Estimated Cost:- Rs. 5,974/-

Date of Completion: 7 days

Name of the work :- Installation of light required for new light post near Barabazar Jagadhatri Gali Under APAS Scheme -- Booth 98 sl no:-12 ward 12

SL No	Description of Work	Qty	Unit	Rate in Rs.	Amount
1	Supply and delivery of 45 watt LED Street Light with pressure die cast aluminium housing, IP66 protection, road way luminarie with high power LED as per the detail technical proposal specification & vendor list attached Make-Crompton /Philips/Havells Warranty Period- 7 Years Ref: Rate Redrive	1	Nos	3579.46	3579.46
2	Fixing outdoor type fluorescent/SV/MV light fitting on pole including S&F 40 mm dia x 1.68 mts. long GI Pipe (ISI-Medium) bracket with 40 mmx10 mm thick, MS clamp etc. and providing wiring with 2x1/1.40 PVC insulated and sheathed wire (single core) from loop box at the base of pole to light fitting through pole & bracket (without control switch) including making connections & painting Ref: PWD(Electrical) Schedule 2017, H-5,H(4)	1	Nos	1335.00	1335.00
	Sub Total			RS	4,914.46
	Add (@18%) Gst			RS	884.60
	Sub Total			RS	5,799.06
	Add (@1%) Cess			RS	57.99
	Total			Rs	5,857.05
	Add (@2%) Contingency			RS	117.14
	Total			Rs	5,974.19

S. J.
17.11.2025
SAE (ELECTRICAL)

CHANDERNAGORE MUNICIPAL CORPORATION

[Signature]
17/11/25
AE (MECHANICAL)

CHANDERNAGORE MUNICIPAL CORPORATION

[Signature]

COMMISSIONER
CHANDERNAGORE MUNICIPAL CORPORATION

[Signature]
MAYOR

CHANDERNAGORE MUNICIPAL CORPORATION

CHANDERNAGORE MUNICIPAL CORPORATION
ESTIMATE

APAS

Estimated Cost:- Rs. 5,974/-

Date of Completion: 7 days

Name of the work :- Installation of light required in front of Saradi Apartment near Barabazar Mishra Lane
Under

APAS Scheme -- Booth 98 sl no:-5 ward 12

SL.No	Description of Work	Qty	Unit	Rate in Rs.	Amount
1	Supply and delivery of 45 watt LED Street Light with pressure die cast aluminium housing, IP66 protection, road way luminarie with high power LED as per the detail technical proposal specification & vendor list attached Make-Crompton /Phillips/Havells Warranty Period- 7 Years Ref: Rate Redrive	1	Nos	3579.46	3579.46
2	Fixing outdoor type fluorescent/SV/MV light fitting on pole including S&F 40 mm dia x 1.68 mts. long GI Pipe (ISI-Medium) bracket with 40 mmx10 mm thick, MS clamp etc. and providing wiring with 2x1/1.40 PVC insulated and sheathed wire (single core) from loop box at the base of pole to light fitting through pole & bracket (without control switch) including making connections & painting Ref: PWD(Electrical) Schedule 2017, H-5,H(4)	1	Nos	1335.00	1335.00
Sub Total				RS	4,914.46
Add (@18%) Gst				RS	884.60
Sub Total				RS	5,799.06
Add (@1%) Cess				RS	57.99
Total				Rs	5,857.05
Add (@2%) Contingency				RS	117.14
Total				Rs	5,974.19

[Signature]
17-11-2025
SAE (ELECTRICAL)

CHANDERNAGORE MUNICIPAL CORPORATION

[Signature]
17/11/25
AE (MECHANICAL)

CHANDERNAGORE MUNICIPAL CORPORATION

[Signature]

COMMISSIONER
CHANDERNAGORE MUNICIPAL CORPORATION

[Signature]
MAYOR

CHANDERNAGORE MUNICIPAL CORPORATION