



CHANDERNAGORE MUNICIPAL CORPORATION

No.IA/Tend/2025-26/262/A

Dated. 04.12.2025

URGENT NOTICE INVITING QUOTATION:

Fund: APAS.

Sealed tenders are invited from the experienced, resourceful and interested Vendors/Suppliers/Contractors to complete the work of the following items required for Electric Dept. under the control of this Corporation individually or unanimously. Vendors/Suppliers/Contractors may participate for both individually or unanimously of the following works.

Quotations are to be given on or before 11.12.2025 within 3 p.m. and will be opened on the same day at 3.30 p.m. Rates should be inclusive of all the taxes and other incidental charges if any. In case of accepted tenderers whose rates have been accepted, fails to supply the required items within the stipulated date & time, necessary items will be purchased from the available sources and the difference in cost will be recovered from the tenderers. The Corporation reserves the right to accept or reject any tender without assigning any reason whatsoever.

Sl. No.	Description of the Items	Booth No	Sl. No.	Ward No.	Quantity Required	Rate Required
1.	Supply & Installation of Electric Pole including supply & fixing of 30 watt LED Street lights in the Corporation Road in front of the house of Shyamashree Chatterjee, Ward No. 10.	108	X	10	One Job	Entire Work
2.	Installation of bright light on existing pole in front of the house of Samir Chandra Manna at Pakre Goli.	48	05	05	One Job	Entire Work

Enco: Estimate of all Works are attached herewith.

PAN, GST and Copy of Trade Enlistment Certificate are Mandatory in this regard.

Ans 04/12/25
Commissioner/Secretary/Finance Officer
Chandernagore Municipal Corporation

No.IA/Tend/2025-26/262/A/1 (12)

Dated. 04.12.2025

Copy to :-

1. Mayor
2. Dy Mayor
3. MMIC (Street Light / Education / Trade Licence / Health / W.W / Sports / Store & Garage)
4. Commissioner/Secretary/Finance Officer
5. Engineer
6. A. O.
7. SAE (Elect)
8. S.A.-1 Please publish in Office Website.
9. Rabindra Bhaban
10. Office Notice Board

Ans 04/12/25
Commissioner/Secretary/Finance Officer
Chandernagore Municipal Corporation

CHANDERNAGORE MUNICIPAL CORPORATION

ESTIMATE

Estimated Cost:- Rs.20,643/-

Date of Completion: 7 days

Name of the work :- Supply & Installation of Electric Pole including supply & fixing of of 30 watt LED street lights in the Corporation Road in front of the house of Shyamashree Chatterjee, Ward No.-10 under Chandernagore Municipal Corporation Under APAS Scheme -- Booth 108

SL No	Description of Work	Qty	Unit	Rate in Rs.	Amount
1	Supplying of Swaged Steel Tubular pole (IS 2713, Pt. II 1980) for following designation and of following dimensions ---- 4 SWG; 5.0 mtrs; 45 Kg Ref: UDMA(E/M) (Vol 1) Schedule 2018, page-3,1 (b)	1	No.	3541	4216
2	Erection of Single Steel tubular pole of length as given below with/without sole plate & Cap etc. in CC foundation (Proportion and dimension indicated below), having 600x600x150 mm thick CC (4:2:1) base block below sole plate/pole with hard jhama metal including CC (6:3:1) muffing 0.30 mts. dia and 0.30 mts. above ground level including 3 mm thick neat cemented finish and GI earth bolt after making drilled holes etc. on pole & carriage of pole upto 1.6 Km from Store to work-site including filling up the excavated earth pit with shifted soil and ramming properly ---- Upto 9.0 mtr. Size 0.6x0.6x1.70 mts Ref: PWD(Electrical) Schedule 2017, H-1, (A)1(a)	1	No.	2835.00	2835.00
3	Extra on items 1 & 2 above, for providing CC (6:3:1) base block (around the pole) dimension 0.45x0.45x0.60 mt. above ground level, neatly cemented finish (3 mm thick), at the base pole (in lieu of CC muffing) suitable for alkathene/ polythene pipe entry as directed for street light wiring, incl. S & F 20cmx15cmx10cm GI Loop box, 16SWG & incl. drilled hole in pole Ref: PWD(Electrical) Schedule 2017, H-1, (A)3(a)(ii)	1	No.	740.00	740.00
4	Painting of Steel Tubular Pole of lengths and no. of coats of paint, as given below with ready mixed paint/primer of approved make, and brand incl. preparation of surface by sand paper/emery paper, cleaning etc. for receiving fresh coat of paint ---- (a) Upto 9.0 mtr. long pole -- (i)1st coat of aluminium paint over 1 coat of RO priming (ii)2nd coat of aluminium paint over 1st coat Ref: PWD(Electrical) Schedule 2017, H-2, (A)4(a)	1	No.	329.00	329.00
5	Supplying of 1.1 KV. Grade PVC insulated Conductor of following cables (make: Polycab/ Gloster/Havells): 2 core 4sqmm Ref: UDMA(E/M) Schedule 2018, page-13, 1(a)1)	29	Mtr	73.00	2117.00
6	Laying of cable upto 2 core 25 sqmm on wall/surface incl. S & F MS saddles with earthing attachment in 10 SWG GI (Hot Dip) Wire, making holes etc. as necy. mending good damages and painting ---- Ref: PWD(Electrical) Schedule 2017, F-1, 2(a)	29	Mtr	57.00	1653.00

7	Supply and delivery of 30 watt LED Street Light with pressure die cast aluminium housing, IP66 protection, road way luminarie with high power LED as per the detail technical proposal specification & vendor list attached [Make-Crompton (LSTS-30-CDL-M)/Philips (BRP042 P LED30 CW S1 PSU GR SPD P4371)/ Havells (ENDURASUNDOWNSL30WLED 757PASYBOPC) Warranty Period- 7 Years]	1	No.	2179.46	2179.46
	Ref: Rate Redrive				
8	Fixing outdoor type fluorescent/SV/MV light fitting on pole including S&F 40 mm dia x 1.68 mts. long GI Pipe (ISI-Medium) bracket with 40 mmx10 mm thick, MS clamp etc. and providing wiring with 2x1/1.40 PVC insulated and sheathed wire (single core) from loop box at the base of pole to light fitting through pole & bracket (without control switch) including making connections & painting	1	No.	1335.00	1335.00
	Ref: PWD(Electrical) Schedule 2014, H-5,H(4)				
9	Supplying and fixing 240/415 V MCB of Breaking capacity 10 KA & C characteristics on din rail of existing DBs and necessary connection --- 6-32 A SPN (Standard)	1	No.	444.00	444.00
	Ref: PWD(Electrical) Schedule 2017, D-7/8				
10	Earthing with 50mm dia GI pipe 3.64mm thick x 3.04mtrs long and 1x4SWG GI (Hot Dip) wire (4mtrs long), 13mm dia x 80mm long GI bolts, double nuts, double washers incl. S&F 15mm dia GI pipe protection (1mtr long) to be filled with bitumen partly under the ground level and partly above ground level driven to an average depth of 3.65mts below the ground level as below: by ISI-Medium GI pipe	1	No.	1369.00	1369.00
	Ref:PWD Schedule (Electrical)2017, Page-G-1/ 2(a)				
11	Supply of 10 SWG GI wire	25	Mtr	3.78	94.50
	Ref:PWD Schedule (Electrical)2017, K-4,sl no 118				
12	Supply of 16 SWG GI wire	9	Mtr	1.00	9.00
	Ref:PWD Schedule (Electrical)2017, K-4,sl no 117				
	Sub Total			RS	17,320.96
	Add (@18%) Gst			RS	3,117.77
	Sub Total			RS	20,438.73
	Add (@1%) Cess			RS	204.39
	Total			Rs	20,643.12
	Say			Rs	20,643

S. In
27.08.2015
SAE (ELECTRICAL)

CHANDERNAGORE MUNICIPAL CORPORATION

Prasanna
27.08.25
AE (MECHANICAL)

CHANDERNAGORE MUNICIPAL CORPORATION

[Signature]
27.08.25
COMMISSIONER

CHANDERNAGORE MUNICIPAL CORPORATION

[Signature]
27/8/25
MAYOR

CHANDERNAGORE MUNICIPAL CORPORATION

APAS (Ward No.4 as found in the portal)

CHANDERNAGORE MUNICIPAL CORPORATION
ESTIMATE

Estimated Cost:- Rs. 5,974/-

Date of Completion: 7 days

Name of the work :- Installation of bright light on existing Pole in front of the house of Samir Chandra Manna at Pakre Goli Under
APAS Scheme -- Booth 48 sl no:-5 ward 5

SL No	Description of Work	Qty	Unit	Rate in Rs.	Amount
1	Supply and delivery of 45 watt LED Street Light with pressure die cast aluminium housing, IP66 protection, road way luminarie with high power LED as per the detail technical proposal specification & vendor list attached Make-Crompton /Philips/Havells Warranty Period- 7 Years Ref: Rate Redrive	1	No.	3579.46	3579.46
2	Fixing outdoor type fluorescent/SV/MV light fitting on pole including S&F 40 mm dia x 1.68 mts. long GI Pipe (ISI-Medium) bracket with 40 mmx10 mm thick, MS clamp etc. and providing wiring with 2x1/1.40 PVC insulated and sheathed wire (single core) from loop box at the base of pole to light fitting through pole & bracket (without control switch) including making connections & painting Ref: PWD(Electrical) Schedule 2017, H-5,H(4)	1	No.	1335.00	1335.00
Sub Total				RS	4,914.46
Add (@18%) Gst				RS	884.60
Sub Total				RS	5,799.06
Add (@1%) Cess				RS	57.99
Total				Rs	5,857.05
Add (@2%) Contingency				RS	117.14
Total				Rs	5,974.19


17.11.2025
SAE (ELECTRICAL)

CHANDERNAGORE MUNICIPAL CORPORATION


17.11.25
AE (MECHANICAL)

CHANDERNAGORE MUNICIPAL CORPORATION



COMMISSIONER
CHANDERNAGORE MUNICIPAL CORPORATION



MAYOR
CHANDERNAGORE MUNICIPAL CORPORATION