



# CHANDERNAGORE MUNICIPAL CORPORATION

No.IA/Tend/2025-26/260

Dated. 04.12.2025

## URGENT NOTICE INVITING QUOTATION:

Fund: APAS.

Sealed tenders are invited from the experienced, resourceful and interested Vendors/Suppliers/Contractors to complete the work of the following items required for Electric Dept. under the control of this Corporation individually or unanimously. Vendors/Suppliers/Contractors may participate for both individually or unanimously of the following works.

Quotations are to be given on or before 11.12.2025 within 3 p.m. and will be opened on the same day at 3.30 p.m. Rates should be inclusive of all the taxes and other incidental charges if any. In case of accepted tenderers whose rates have been accepted, fails to supply the required items within the stipulated date & time, necessary items will be purchased from the available sources and the difference in cost will be recovered from the tenderers. The Corporation reserves the right to accept or reject any tender without assigning any reason whatsoever.

Sl. No.	Description of the Items	Booth No	Sl. No.	Ward No.	Quantity Required	Rate Required
1.	Construction of Temporary Fencing and bright LED light at Goswami Ghat Durga Puja adjacent area.	42	03	4	One Job	Entire Work

**Encl: Estimate of all Works are attached herewith.**

PAN, GST and Copy of Trade Enlistment Certificate are Mandatory in this regard.

*[Signature]*  
Commissioner/Secretary/Finance Officer  
Chandernagore Municipal Corporation

Secretary  
Chandannagar Municipal  
Corporation

No.IA/Tend/2025-26/260/1 (12)

Dated. 04.12.2025

**Copy to :-**

1. Mayor
2. Dy Mayor
3. MMIC ( Street Light / Education / Trade Licence / Health / W.W / Sports / Store & Garage )
4. Commissioner/Secretary/Finance Officer
5. Engineer
6. A. O.
7. SAE (Elect)
8. S.A.-1 Please publish in Office Website.
9. Rabindra Bhaban
10. Office Notice Board

*[Signature]*  
Commissioner/Secretary/Finance Officer  
Chandernagore Municipal Corporation

Secretary  
Chandannagar Municipal  
Corporation

**CHANDERNAGORE MUNICIPAL CORPORATION**  
**ESTIMATE**

APAS

Estimated Cost:- Rs.97,924/-

Date of Completion: 10 days

Name of the work :- Construction of Temporary Fencing and bright LED light at Goswami Ghat Durga Puja adjacent area [ Electrical work ] under APAS Scheme -- Booth 42 sl no 04 ward no 04

SL No	Description of Work	Qty	Unit	Rate in Rs.	Amount
1	Supplying of Swaged Steel Tubular pole (IS 2713, Pt. II 1980) for following designation and of following dimensions ---- 410-SP-33; 9.0mtrs: 164 Kg Ref: UDMA(E/M) (Vol 1) Schedule 2018, page-3,1 (j)	1	No.	14238	14238
3	Erection of Single Steel tubular pole of length as given below with/without sole plate & Cap etc. in CC foundation (Proportion and dimension indicated below), having 600x600x150 mm thick CC (4:2:1) base block below sole plate/pole with hard jhama metal including CC (6:3:1) muffing 0.30 mts. dia and 0.30 mts. above ground level including 3 mm thick neat cemented finish and GI earth bolt after making drilled holes etc. on pole & carriage of pole upto 1.6 Km from Store to work-site including filling up the excavated earth pit with shifted soil and ramming properly ---- Upto 9.0 mtr. Size 0.6x0.6x1.70 mts Ref: PWD(Electrical) Schedule 2017, H-1, (A)1(a)	1	No.	2835.00	2835.00
4	Extra on items 1 & 2 above, for providing CC (6:3:1) base block (around the pole) dimension 0.45x0.45x0.60 mt. above ground level, neatly cemented finish (3 mm thick), at the base pole (in lieu of CC muffing) suitable for alkathene/ polythene pipe entry as directed for street light wiring, incl. S & F 20cmx15cmx10cm GI Loop box, 16SWG & incl. drilled hole in pole [ 1 for 9 Mtr Pole & 8 for others ] Ref: PWD(Electrical) Schedule 2017, H-1, (A)3(a)(ii)	9	Nos	740.00	6660.00
5	Painting of Steel Tubular Pole of lengths and no. of coats of paint, as given below with ready mixed paint/primer of approved make, and brand incl. preparation of surface by sand paper/emery paper, cleaning etc. for receiving fresh coat of paint ---- (a) Upto 9.0 mtr. long pole -- (i)1st coat of aluminium paint over 1 coat of RO priming (ii)2nd coat of aluminium paint over 1st coat Ref: PWD(Electrical) Schedule 2017, H-2, (A)4(a)	1	No.	329.00	329.00
6	Supplying of 1.1 KV. Grade PVC insulated Conductor of following cables (make: Polycab/ Gloster/Havells): 2 core 4sqmm Ref: UDMA(E/M) Schedule 2018, page-11, 1(a)1	93	Mtr	73.00	6789.00
7	Laying of cable upto 2 core 25 sqmm on wall/surface incl. S & F MS saddles with earthing attachment in 10 SWG GI (Hot Dip) Wire, making holes etc. as necy. mending good damages and painting ---- Ref: PWD(Electrical) Schedule 2017, F-1, 2(a)	93	Mtr	57.00	5301.00
8	Supply and delivery of 90 watt LED Street Light with pressure die cast aluminium housing, IP66 protection, road way luminarie with high power LED as per the detail technical proposal specification & vendor list attached [ Make-Crompton /Philips / Havells ) Warranty Period- 7 Years]	1	No.	6458.04	6458.04

Ref: Rate Redrive					
9	Fixing outdoor type fluorescent/SV/MV light fitting on pole including S&F 40 mm dia x 1.68 mts. long GI Pipe (ISI-Medium) bracket with 40 mmx10 mm thick, MS clamp etc. and providing wiring with 2x1/1.40 PVC insulated and sheathed wire (single core) from loop box at the base of pole to light fitting through pole & bracket (without control switch) including making connections & painting   1 for 90W LED SL and 8 for LED Post Top Lantern ]	9	Nos	1335.00	12015.00
Ref: PWD(Electrical) Schedule 2017, H-5,H(4)					
10	Supplying and fixing 240/415 V MCB of Breaking capacity 10 KA & C characteristics on din rail of existing DBs and necessary connection --- 6-32 A SPN ( Standard )   1 for 9Mtr Pole and 1 for others	2	Nos	444.00	888.00
Ref: PWD(Electrical) Schedule 2017, D-7/8					
11	Earthing with 50mm dia GI pipe 3.64mm thick x 3.04mtrs long and 1x4SWG GI (Hot Dip) wire (4mtrs long), 13mm dia x 80mm long GI bolts, double nuts, double washers incl. S&F 15mm dia GI pipe protection (1mtr long) to be filled with bitumen partly under the ground level and partly above ground level driven to an average depth of 3.65mtrs below the ground level as below: by ISI-Medium GI Pipe   1 for 9Mtr Pole and 1 for others	2	Nos	1369.00	2738.00
Ref:PWD Schedule (Electrical)2017, Page-G-1/ 2(a)					
12	Supply of Post Top Lantern Fittings with Lamp (IP65)-- LED Inground , min Lumen output:- 500watt	8	No.	2620.00	20960.00
Ref: Rate Analysis					
13	50mm heavy gauge Polythene Pipe	32	Mtr	42.00	1344.00
Ref: PWD(Electrical) Schedule 2014, K-2, sl no 55					
Sub Total				RS	80,555.04
Add (@18%) Gst				RS	14,499.91
Sub Total				RS	95,054.95
Add (@1%) Cess				RS	950.55
Total				Rs	96,005.50
Add (@2%) Contingency				RS	1,920.11
Total				Rs	97,925.61

*S. L.*

24.11.2025

SAE (ELECTRICAL)

CHANDERNAGORE MUNICIPAL CORPORATION

Sub-Asstt. Engineer (Elec.)  
Chandernagore Municipal  
Corporation

*SOP*

COMMISSIONER

CHANDERNAGORE MUNICIPAL CORPORATION

Commissioner  
Chandernagore Municipal  
Corporation

AE (MECHANICAL)

CHANDERNAGORE MUNICIPAL  
CORPORATION

Asstt. Engineer (Mech.)  
Chandernagore Municipal  
Corporation

MAYOR

CHANDERNAGORE MUNICIPAL  
CORPORATION

Mayor  
Chandernagore  
Municipal Corporation