



CHANDERNAGORE MUNICIPAL CORPORATION

No.IA/Tend/2025-26/194/G

Dated. 11.11.2025

URGENT NOTICE INVITING QUOTATION:

Fund: Line Dept. Govt. Grant.

Sealed tenders are invited from the experienced, resourceful and interested Vendors/Suppliers/Contractors to complete the work of the following items required for Electric Dept. under the control of this Corporation individually or unanimously. Vendors/Suppliers/Contractors may participate for both individually or unanimously of the following works.

Quotations are to be given on or before 18.11.2025 within 3 p.m. and will be opened on the same day at 3.30 p.m. Rates should be inclusive of all the taxes and other incidental charges if any. In case of accepted tenderers whose rates have been accepted, fails to supply the required items within the stipulated date & time, necessary items will be purchased from the available sources and the difference in cost will be recovered from the tenderers. The Corporation reserves the right to accept or reject any tender without assigning any reason whatsoever.

Sl. No.	Description of the Items	Booth No	Sl. No.	Ward No.	Quantity Required	Rate Required
1.	Arrangement of LED light and electric pole in front of house of Sudip Saha at Gopalbag Bye lane.	123	07	18	One Job	Entire Work

Enclo: Estimate of all Works are attached herewith.

Laying of cables upto 2 core 22 sqmm on wall surfaces and 10 40 P 1/2 cables with earthing attachment in 10 SWG GI (Hot Dip) Wire, making holes etc. as necessary mending good damages and painting.

PAN, GST and Copy of Trade Enlistment Certificate are Mandatory in this regard.



Commissioner/Secretary/Finance Officer
Chandernagore Municipal Corporation

No.IA/Tend/2025-26/194/G/1 (12)

Dated. 11.11.2025

Copy to :-

1. Mayor
2. Dy Mayor
3. MMIC (Street Light / Education / Trade Licence / Health / W.W / Sports / Store & Garage)
4. Commissioner/Secretary/Finance Officer
5. Engineer
6. A. O.
7. SAE (Elect)
8. S.A.-1 Please publish in Office Website.
9. Office Notice Board


Commissioner/Secretary/Finance Officer
Chandernagore Municipal Corporation

CHANDERNAGORE MUNICIPAL CORPORATION
ESTIMATE

Line Dept


Estimated Cost:- Rs. ~~41,131/-~~ *41,193/-*


Date of Completion: 7 days


Name of the work :- Arrangement of LED light and electric pole in front of house of Sudip Saha at Gopalbag Bye lane
Under APAS Scheme -- Booth 123_sl no 7_w18

SL No	Description of Work	Qty	Unit	Rate in Rs.	Amount
1	Supplying of Swaged Steel Tubular pole (IS 2713, Pt. II 1980) for following designation and of following dimensions ---- 410-SP-33; 9.0mtrs: 164 Kg Ref: UDMA(E/M) (Vol 1) Schedule 2018, page-3,1 (d)	1	No.	14238	14238
2	S/F single arm projected lamp bracket (Single pipe bending) of 50cm (2") dia G.I. pipe (ISI medium) 3.65 mm thick of 2.1 mtr (6' approx) long having 105 degree curvature with reducing socket to be fitted at the top of the pole with bolts, nuts, clamps etc. as required. Ref: UDMA(E/M) (Vol 1) Schedule 2018, page-5, 22	1	No.	881	4216
3	Erection of Single Steel tubular pole of length as given below with/without sole plate & Cap etc. in CC foundation (Proportion and dimension indicated below), having 600x600x150 mm thick CC (4:2:1) base block below sole plate/pole with hard jhama metal including CC (6:3:1) muffing 0.30 mts. dia and 0.30 mts. above ground level including 3 mm thick neat cemented finish and GI earth bolt after making drilled holes etc. on pole & carriage of pole upto 1.6 Km from Store to work-site including filling up the excavated earth pit with shifted soil and ramming properly ---- Upto 9.0 mtr. Size 0.6x0.6x1.70 mts Ref: PWD(Electrical) Schedule 2017, H-1, (A)1(a)	1	No.	2835.00	2835.00
4	Extra on items 1 & 2 above, for providing CC (6:3:1) base block (around the pole) dimension 0.45x0.45x0.60 mt. above ground level, neatly cemented finish (3 mm thick), at the base pole (in lieu of CC muffing) suitable for alkathene/ polythene pipe entry as directed for street light wiring, incl. S & F 20cmx15cmx10cm GI Loop box, 16SWG & incl. drilled hole in pole Ref: PWD(Electrical) Schedule 2017, H-1, (A)3(a)(ii)	1	No.	740.00	740.00
5	Painting of Steel Tubular Pole of lengths and no. of coats of paint, as given below with ready mixed paint/primer of approved make, and brand incl. preparation of surface by sand paper/emery paper, cleaning etc. for receiving fresh coat of paint ---- (a) Upto 9.0 mtr. long pole -- (i)1st coat of aluminium paint over 1 coat of RO priming (ii)2nd coat of aluminium paint over 1st coat Ref: PWD(Electrical) Schedule 2017, H-2, (A)4(a)	1	No.	329.00	329.00
6	Supplying of 1.1 KV. Grade PVC insulated Conductor of following cables (make: Polycab/ Gloster/Havells): 2 core 4sqmm Ref: UDMA(E/M) Schedule 2018, page-13, 1(a)1)	20	Mtr	73.00	1460.00
7	Laying of cable upto 2 core 25 sqmm on wall/surface incl. S & F MS saddles with earthing attachment in 10 SWG GI (Hot Dip) Wire, making holes etc. as necy. mending good damages and painting ---- Ref: PWD(Electrical) Schedule 2017, F-1, 2(a)	20	Mtr	57.00	1140.00

Supply and delivery of 90 watt LED Street Light with pressure die cast aluminium housing, IP66 protection, road way luminaire with high power LED as per the detail technical proposal specification & vendor list attached [Make-Crompton /Philips/ Havells] Warranty Period- 7 Years		1	No.	6458.04	6458.04
Ref: Rate Redrive					
9	Fixing outdoor type fluorescent/SV/MV light fitting on pole including S&F 40 mm dia x 1.68 mts. long GI Pipe (ISI-Medium) bracket with 40 mmx10 mm thick, MS clamp etc. and providing wiring with 2x1/1.40 PVC insulated and sheathed wire (single core) from loop box at the base of pole to light fitting through pole & bracket (without control switch) including making connections & painting	1	No.	1335.00	1335.00
Ref: PWD(Electrical) Schedule 2014, H-5,H(4)					
10	Supplying and fixing 240/415 V MCB of Breaking capacity 10 KA & C characteristics on din rail of existing DBs and necessary connection --- 6-32 A SPN (Standard)	1	No.	444.00	444.00
Ref: PWD(Electrical) Schedule 2017, D-7/8					
11	Earthing with 50mm dia GI pipe 3.64mm thick x 3.04mtrs long and 1x4SWG GI (Hot Dip) wire (4mtrs long), 13mm dia x 80mm long GI bolts, double nuts, double washers incl. S&F 15mm dia GI pipe protection (1mtr long) to be filled with bitumen partly under the ground level and partly above ground level driven to an average depth of 3.65mts below the ground level as below: by ISI-Medium GI pipe	1	No.	1369.00	1369.00
Ref:PWD Schedule (Electrical)2017, Page-G-1/ 2(a)					
Sub Total				RS	34,564.04
Add (@18%) Gst				RS	6,221.53
Sub Total				RS	40,785.57
Add (@1%) Cess				RS	345.64 40786
Total				Rs	41,131.21 41193 42
Say				Rs	41,131 41193


 10.09.2025
 SAE (ELECTRICAL)
 CHANDERNAGORE MUNICIPAL CORPORATION


 AE (MECHANICAL) 10/09/25
 CHANDERNAGORE MUNICIPAL CORPORATION


 COMMISSIONER
 CHANDERNAGORE MUNICIPAL CORPORATION


 MAYOR
 CHANDERNAGORE MUNICIPAL CORPORATION