



CHANDERNAGOFE MUNICIPAL CORPORATION

No.IA/Tend/2025-26/226

Dated. 28.11.2025

URGENT NOTICE INVITING QUOTATION:

Fund: APAS.


Sealed tenders are invited from the experienced, resourceful and interested Vendors/Suppliers/Contractors to complete the work of the following items required for Electric Dept. under the control of this Corporation individually or unanimously. Vendors/Suppliers/Contractors may participate for both individually or unanimously of the following works.

Quotations are to be given on or before 05.12.2025 within 3 p.m. and will be opened on the same day at 3.30 p.m. Rates should be inclusive of all the taxes and other incidental charges if any. In case of accepted tenderers whose rates have been accepted, fails to supply the required items within the stipulated date & time, necessary items will be purchased from the available sources and the difference in cost will be recovered from the tenderers. The Corporation reserves the right to accept or reject any tender without assigning any reason whatsoever.

Sl. No.	Description of the Items	Booth No	Sl. No.	Ward No.	Quantity Required	Rate Required
1.	Installation of electric pole with Bright Light beside Mitali Sangha Club.	25	03	01	One Job	Entire Work
2.	Enhancement of illumination in front of the house of Pranab Moshari at bauri Para.	17	14	09	One Job	Entire Work
3.	Installation of electric pole with Bright Light from the house of Kamal Ray to H.P. Cas at bauripara.	18	04	09	One Job	Entire Work
4.	Enhancement of illumination in front of the house of Surajit Sen at Nanda Ghosh 1 st Lane.	19	08	09	One Job	Entire Work
5.	Enhancement of illumination in front of the house of Gopal Biswas at Kalupukur Kumorpara 2 nd Lane.	19	10	09	One Job	Entire Work
6.	Installation of Bright LED Light in front of Amal Mukherjee nea Durgamandir at Manna Pukur 1 st Lane.	21	07	01	One Job	Entire Work
7.	Enhancement of illumination in front Mohan Sangha Club at Daspuurkudhar.	22	06	01	One Job	Entire Work

Encl: Estimate of all Works are attached herewith.

PAN, GST and Copy of Trade Enlistment Certificate are Mandatory in this regard.


Commissioner/Secretary/Finance Officer
Chandernagore Municipal Corporation

Secretary

Chandannagar Municipal
Corporation

No.IA/Tend/2025-26/226/1 (12)

Dated. 28.11.2025

Copy to :-

1. Mayor
2. Dy Mayor
3. MMIC (Street Light / Education / Trade Licence / Health / W.W / Sports / Store & Garage)
4. Commissioner/Secretary/Finance Officer
5. Engineer
6. A. O.
7. SAE (Elect)
8. S.A.-1 Please publish in Office Website.
9. Rabindra Bhaban
10. Office Notice Board


Commissioner/Secretary/Finance Officer
Chandernagore Municipal Corporation

Secretary

Chandannagar Municipal
Corporation

APAS

CHANDERNAGORE MUNICIPAL CORPORATION
ESTIMATE

Estimated Cost:- Rs.54,135/-

Date of Completion: 10 days

Name of the work :- Installation of electric pole with bright light beside of Mitali Sangha Club under
APAS Scheme -- Booth 25 sl no 03 ward no 01

SL No	Description of Work	Qty	Unit	Rate in Rs.	Amount
1	Supplying of Swaged Steel Tubular pole (IS 2713, Pt. II 1980) for following designation and of following dimensions ---- 410-SP-33; 9.0mtrs: 164 Kg Ref: UDMA(E/M) (Vol 1) Schedule 2018, page-3,1 (j)	1	No.	14238	14238
2	S/F double arm projected lamp bracket (Single pipe bending) of 50mm (2") dia G.I. pipe (ISI medium) of 2.5 mtr long each having 105 degree curvature with reducing socket to be fitted at the top of the pole with bolts, nuts clamps etc. as required Ref: UDMA(E/M) (Vol 1) Schedule 2018, page-5, 23	1	No.	2491	2491
3	Erection of Single Steel tubular pole of length as given below with/without sole plate & Cap etc. in CC foundation (Proportion and dimension indicated below), having 600x600x150 mm thick CC (4:2:1) base block below sole plate/pole with hard jhama metal including CC (6:3:1) muffing 0.30 mts. dia and 0.30 mts. above ground level including 3 mm thick neat cemented finish and GI earth bolt after making drilled holes etc. on pole & carriage of pole upto 1.6 Km from Store to work-site including filling up the excavated earth pit with shifted soil and ramming properly ---- Upto 9.0 mtr. Size 0.6x0.6x1.70 mts Ref: PWD(Electrical) Schedule 2017, H-1, (A)1(a)	1	No.	2835.00	2835.00
4	Extra on items 1& 2 above, for providing CC (6:3:1) base block (around the pole) dimension 0.45x0.45x0.60 mt. above ground level, neatly cemented finish (3 mm thick), at the base pole (in lieu of CC muffing) suitable for alkathene/ polythene pipe entry as directed for street light wiring, incl. S & F 20cmx15cmx10cm GI Loop box, 16SWG & incl. drilled hole in pole Ref: PWD(Electrical) Schedule 2017, H-1, (A)3(a)(ii)	1	No.	740.00	740.00
5	Painting of Steel Tubular Pole of lengths and no. of coats of paint, as given below with ready mixed paint/primer of approved make, and brand incl. preparation of surface by sand paper/emery paper, cleaning etc. for receiving fresh coat of paint ---- (a) Upto 9.0 mtr. long pole -- (i)1st coat of aluminium paint over 1 coat of RO priming (ii)2nd coat of aluminium paint over 1st coat Ref: PWD(Electrical) Schedule 2017, H-2, (A)4(a)	1	No.	329.00	329.00
6	Supplying of 1.1 KV. Grade PVC insulated Conductor of following cables (make: Polycab/ Gloster/Havells): 2 core 4sqmm Ref: UDMA(E/M) Schedule 2018, page-11, 1(a)1	50	Mtr	73.00	3650.00
7	Laying of cable upto 2 core 25 sqmm on wall/surface incl. S & F MS saddles with earthing attachment in 10 SWG GI (Hot Dip) Wire, making holes etc. as necy. mending good damages and painting ----	50	Mtr	57.00	2850.00

	Ref: PWD(Electrical) Schedule 2017, F-1, 2(a)				
8	Supply and delivery of 90 watt LED Street Light with pressure die cast aluminium housing, IP66 protection, road way luminarie with high power LED as per the detail technical proposal specification & vendor list attached Make-Crompton /Philips / Havells) Warranty Period- 7 Years]	2	Nos	6458.04	12916.08
	Ref: Rate Redrive				
9	Fixing outdoor type fluorescent/SV/MV light fitting on pole including S&F 40 mm dia x 1.68 mts. long GI Pipe (ISI-Medium) bracket with 40 mmx10 mm thick, MS clamp etc. and providing wiring with 2x1/1.40 PVC insulated and sheathed wire (single core) from loop box at the base of pole to light fitting through pole & bracket (without control switch) including making connections & painting	2	Nos	1335.00	2670.00
	Ref: PWD(Electrical) Schedule 2017, H-5,H(4)				
10	Supplying and fixing 240/415 V MCB of Breaking capacity 10 KA & C characteristics on din rail of existing DBs and necessary connection --- 6-32 A SPN (Standard)	1	No.	444.00	444.00
	Ref: PWD(Electrical) Schedule 2017, D-7/8				
11	Earthing with 50mm dia GI pipe 3.64mm thick x 3.04mtrs long and 1x4SWG GI (Hot Dip) wire (4mtrs long), 13mm dia x 80mm long GI bolts, double nuts, double washers incl. S&F 15mm dia GI pipe protection (1mtr long) to be filled with bitumen partly under the ground level and partly above ground level driven to an average depth of 3.65mts below the ground level as below: by ISI-Medium GI pipe	1	No.	1369.00	1369.00
	Ref:PWD Schedule (Electrical)2017, Page-G-1/ 2(a)				
	Sub Total			RS	44,532.08
	Add (@18%) Gst			RS	8,015.77
	Sub Total			RS	52,547.85
	Add (@1%) Cess			RS	525.48
	Total			Rs	53,073.33
	Add (@2%) Contingency			RS	1,061.47
	Total			Rs	54,134.80
	Say			Rs	54,135


 21.11.2025
 SAE (ELECTRICAL)
 CHANDERNAGORE MUNICIPAL CORPORATION


 21/11/25
 AE (MECHANICAL)
 CHANDERNAGORE MUNICIPAL CORPORATION


 COMMISSIONER
 CHANDERNAGORE MUNICIPAL CORPORATION


 MAYOR
 CHANDERNAGORE MUNICIPAL CORPORATION

CHANDERNAGORE MUNICIPAL CORPORATION
ESTIMATE

APAS

Estimated Cost:- Rs. 4,272/-

Date of Completion: 7 days

Name of the work :- Enhancement of illumination in front of the house of Pranab Moshari at
Bauripara Under
APAS Scheme -- Booth 17 sl no:-14 ward 09

SL No	Description of Work	Qty	Unit	Rate in Rs.	Amount
1	Supply and delivery of 30 watt LED Street Light with pressure die cast aluminium housing, IP66 protection, road way luminarie with high power LED as per the detail technical proposal specification & vendor list attached [Make-Crompton /Philips/Havells Warranty Period- 7 Years]	1	No.	2179.46	2179.46
	Ref: Rate Redrive				
2	Fixing outdoor type fluorescent/SV/MV light fitting on pole including S&F 40 mm dia x 1.68 mts. long GI Pipe (ISI-Medium) bracket with 40 mmx10 mm thick, MS clamp etc. and providing wiring with 2x1/1.40 PVC insulated and sheathed wire (single core) from loop box at the base of pole to light fitting through pole & bracket (without control switch) including making connections & painting	1	No.	1335.00	1335.00
	Ref: PWD(Electrical) Schedule 2014, H-5,H(4)				
	Sub Total			RS	3,514.46
	Add (@18%) Gst			RS	632.60
	Sub Total			RS	4,147.06
	Add (@1%) Cess			RS	41.47
	Total			Rs	4,188.53
	Add (@2%) Contingency			RS	83.77
	Total			Rs	4,272.30

S. Jm
17.11.2025
SAE (ELECTRICAL)

CHANDERNAGORE MUNICIPAL CORPORATION

Pragat
17/11/25
AE (MECHANICAL)

CHANDERNAGORE MUNICIPAL CORPORATION

[Signature]
COMMISSIONER
CHANDERNAGORE MUNICIPAL CORPORATION

[Signature]
MAYOR
CHANDERNAGORE MUNICIPAL CORPORATION

APAS

CHANDERNAGORE MUNICIPAL CORPORATION
ESTIMATE

Estimated Cost:- Rs.8,545/-

Date of Completion: 7 days

Name of the work :- Installation of Electric pole with bright LED light from the house of Kamal Roy to H.P.Gas Goli at Bauripara Area Under APAS Scheme -- Booth 18_sl no 04_w 9

SL No	Description of Work	Qty	Unit	Rate in Rs.	Amount
1	Supply and delivery of 30 watt LED Street Light with pressure die cast aluminium housing, IP66 protection, road way luminarie with high power LED as per the detail technical proposal specification & vendor list attached Make-Crompton /Philips Havells Warranty Period- 7 Years	2	Nos	2179.46	4358.92
	Ref: Rate Redrive				
2	Fixing outdoor type fluorescent/SV/MV light fitting on pole including S&F 40 mm dia x 1.68 mts. long GI Pipe (ISI-Medium) bracket with 40 mmx10 mm thick, MS clamp etc. and providing wiring with 2x1/1.40 PVC insulated and sheathed wire (single core) from loop box at the base of pole to light fitting through pole & bracket (without control switch) including making connections & painting Ref: PWD (Electrical) Schedule 2014, H-5, H (4)	2	Nos	1335.00	2670.00
	Sub Total			RS	7,028.92
	Add (@18%) Gst			RS	1,265.21
	Sub Total			RS	8,294.13
	Add (@1%) Cess			RS	82.94
	Total			Rs	8,377.07
	Add (@2%) Contingency			RS	167.54
	Total			Rs	8,544.61

[Signature]
17.11.2025

SAE (ELECTRICAL)

CHANDERNAGORE MUNICIPAL CORPORATION

[Signature]
17/11/25

AE (MECHANICAL)

CHANDERNAGORE MUNICIPAL CORPORATION

[Signature]

COMMISSIONER
CHANDERNAGORE MUNICIPAL CORPORATION

[Signature]

MAYOR
CHANDERNAGORE MUNICIPAL CORPORATION

CHANDERNAGORE MUNICIPAL CORPORATION

ESTIMATE


Estimated Cost:- Rs.4,272/-

Date of Completion: 7 days

APAS

Name of the work :- Enhancement of illumination in front of the house of Surajit Sen at Nanda Ghosh
1st Lane Under
APAS Scheme -- Booth 19_sl no 08_w 9

SL No	Description of Work	Qty	Unit	Rate in Rs.	Amount
1	Supply and delivery of 30 watt LED Street Light with pressure die cast aluminium housing, IP66 protection, road way luminarie with high power LED as per the detail technical proposal specification & vendor list attached Make-Crompton /Philips Havells Warranty Period- 7 Years	1	No.	2179.46	2179.46
	Ref: Rate Redrive				
2	Fixing outdoor type fluorescent/SV/MV light fitting on pole including S&F 40 mm dia x 1.68 mts. long GI Pipe (ISI-Medium) bracket with 40 mmx10 mm thick, MS clamp etc. and providing wiring with 2x1/1.40 PVC insulated and sheathed wire (single core) from loop box at the base of pole to light fitting through pole & bracket (without control switch) including making connections & painting Ref: PWD (Electrical) Schedule 2014, H-5, H(4)	1	No.	1335.00	1335.00
	Sub Total			RS	3,514.46
	Add (@18%) Gst			RS	632.60
	Sub Total			RS	4,147.06
	Add (@1%) Cess			RS	41.47
	Total			Rs	4,188.53
	Add (@2%) Contingency			RS	83.77
	Total			Rs	4,272.30



17.11.2025
SAE (ELECTRICAL)

CHANDERNAGORE MUNICIPAL CORPORATION


17/11/25
AE (MECHANICAL)

CHANDERNAGORE MUNICIPAL CORPORATION


COMMISSIONER
CHANDERNAGORE MUNICIPAL CORPORATION


MAYOR
CHANDERNAGORE MUNICIPAL CORPORATION

CHANDERNAGORE MUNICIPAL CORPORATION
ESTIMATE

APAS

Estimated Cost:- Rs.12,817/-

Date of Completion: 7 days

Name of the work :- Enhancement of illumination in front of the house of Gopal Biswas at Kalupukur
Kumorpara 2nd Lane Under
APAS Scheme -- Booth 19_sl no 10_w 9

Sl.No	Description of Work	Qty	Unit	Rate in Rs.	Amount
1	Supply and delivery of 30 watt LED Street Light with pressure die cast aluminium housing, IP66 protection, road way luminarie with high power LED as per the detail technical proposal specification & vendor list attached [Make-Crompton /Philips Havells] Warranty Period- 7 Years	3	Nos	2179.46	6538.38
	Ref: Rate Redrive				
2	Fixing outdoor type fluorescent/SV/MV light fitting on pole including S&F 40 mm dia x 1.68 mts. long GI Pipe (ISI-Medium) bracket with 40 mmx10 mm thick, MS clamp etc. and providing wiring with 2x1/1.40 PVC insulated and sheathed wire (single core) from loop box at the base of pole to light fitting through pole & bracket (without control switch) including making connections & painting Ref: PWD (Electrical) Schedule 2014, H-5, H(4)	3	Nos	1335.00	4005.00
	Sub Total			RS	10,543.38
	Add (@18%) Gst			RS	1,897.81
	Sub Total			RS	12,441.19
	Add (@1%) Cess			RS	124.41
	Total			Rs	12,565.60
	Add (@2%) Contingency			RS	251.31
	Total			Rs	12,816.91

[Signature]
17/11/2025
SAE (ELECTRICAL)

CHANDERNAGORE MUNICIPAL CORPORATION

[Signature]
17/11/25
AE (MECHANICAL)

CHANDERNAGORE MUNICIPAL CORPORATION

[Signature]
COMMISSIONER
CHANDERNAGORE MUNICIPAL CORPORATION

[Signature]
MAYOR
CHANDERNAGORE MUNICIPAL CORPORATION

CHANDERNAGORE MUNICIPAL CORPORATION
ESTIMATE

APAS

Estimated Cost:- Rs. 5,974/-

Date of Completion: 7 days

Name of the work :- Installation of bright LED Light in front house of Amal Mukherjee near Durgamandir at Mannapukur 1st Lane Under APAS Scheme -- Booth 21 sl no:-07 ward 01

SL No	Description of Work	Qty	Unit	Rate in Rs.	Amount
1	Supply and delivery of 45 watt LED Street Light with pressure die cast aluminium housing, IP66 protection, road way luminarie with high power LED as per the detail technical proposal specification & vendor list attached [Make-Crompton /Philips/Havells Warranty Period- 7 Years	1	No.	3579.46	3579.46
	Ref: Rate Redrive				
2	Fixing outdoor type fluorescent/SV/MV light fitting on pole including S&F 40 mm dia x 1.68 mts. long GI Pipe (ISI-Medium) bracket with 40 mmx10 mm thick, MS clamp etc. and providing wiring with 2x1/L.40 PVC insulated and sheathed wire (single core) from loop box at the base of pole to light fitting through pole & bracket (without control switch) including making connections & painting	1	No.	1335.00	1335.00
	Ref: PWD(Electrical) Schedule 2014, H-5,H(4)				
	Sub Total			RS	4,914.46
	Add (@18%) Gst			RS	884.60
	Sub Total			RS	5,799.06
	Add (@1%) Cess			RS	57.99
	Total			Rs	5,857.05
	Add (@2%) Contingency			RS	117.14
	Total			Rs	5,974.19

G. Jm
17.11.2025
SAE (ELECTRICAL)

CHANDERNAGORE MUNICIPAL CORPORATION

[Signature]
17/11/25
AE (MECHANICAL)

CHANDERNAGORE MUNICIPAL CORPORATION

[Signature]
COMMISSIONER
CHANDERNAGORE MUNICIPAL CORPORATION

[Signature]
MAYOR
CHANDERNAGORE MUNICIPAL CORPORATION

CHANDERNAGORE MUNICIPAL CORPORATION
ESTIMATE

APAS

Estimated Cost:- Rs. 5,974/-

Date of Completion: 7 days

Name of the work :- Enhancement of illumination in front Mohan Sangha Club at Daspukurdhar Under
APAS Scheme – Booth 22 sl no:-06 ward 01

SL No	Description of Work	Qty	Unit	Rate in Rs.	Amount
1	Supply and delivery of 45 watt LED Street Light with pressure die cast aluminium housing, IP66 protection, road way luminarie with high power LED as per the detail technical proposal specification & vendor list attached Make-Crompton /Philips/Havells Warranty Period- 7 Years Ref: Rate Redrive	1	No.	3579.46	3579.46
2	Fixing outdoor type fluorescent/SV/MV light fitting on pole including S&F 40 mm dia x 1.68 mts. long GI Pipe (ISI-Medium) bracket with 40 mmx10 mm thick, MS clamp etc. and providing wiring with 2x1/1.40 PVC insulated and sheathed wire (single core) from loop box at the base of pole to light fitting through pole & bracket (without control switch) including making connections & painting Ref: PWD(Electrical) Schedule 2014, H-5,H(4)	1	No.	1335.00	1335.00
Sub Total				RS	4,914.46
Add (@18%) Gst				RS	884.60
Sub Total				RS	5,799.06
Add (@1%) Cess				RS	57.99
Total				Rs	5,857.05
Add (@2%) Contingency				RS	117.14
Total				Rs	5,974.19

S. L.
17.11.2025
SAE (ELECTRICAL)

CHANDERNAGORE MUNICIPAL CORPORATION

[Signature]
17/11/25
AE (MECHANICAL)

CHANDERNAGORE MUNICIPAL CORPORATION

[Signature]

COMMISSIONER
CHANDERNAGORE MUNICIPAL CORPORATION

[Signature]
MAYOR

CHANDERNAGORE MUNICIPAL CORPORATION