



CHANDERNAGORE MUNICIPAL CORPORATION

No.IA/Tend/2025-26/194/F

Dated. 11.11.2025

URGENT NOTICE INVITING QUOTATION:

Fund: Line Dept. Govt. Grant.

Sealed tenders are invited from the experienced, resourceful and interested Vendors/Suppliers/Contractors to complete the work of the following items required for Electric Dept. under the control of this Corporation individually or unanimously. Vendors/Suppliers/Contractors may participate for both individually or unanimously of the following works.

Quotations are to be given on or before 18.11.2025 within 3 p.m. and will be opened on the same day at 3.30 p.m. Rates should be inclusive of all the taxes and other incidental charges if any. In case of accepted tenderers whose rates have been accepted, fails to supply the required items within the stipulated date & time, necessary items will be purchased from the available sources and the difference in cost will be recovered from the tenderers. The Corporation reserves the right to accept or reject any tender without assigning any reason whatsoever.

Sl. No.	Description of the Items	Booth No	Sl. No.	Ward No.	Quantity Required	Rate Required
1.	Installation of sufficient light from the house of Sipra Das to Ashis Chowdhuri at Brahminpara.	63	5	31	One Job	Entire Work
2.	Installation of iron pole with 45 watt light infront of Arup Kumar Kundu at Sabinara main Road	122	07	18	One Job	Entire Work
3.	Installation of light opposite of the house of Kajol Chatterjee at Boral bagan.	110	15	10	One Job	Entire Work
4.	Installation of light from House of Pulin Mitra to House of Anil Mitra.	109	10	10	One Job	Entire Work
5.	Installation of electric pole with light infront of Bidhan Smriti School.	121	05	18	One Job	Entire Work

Encls: Estimate of all Works are attached herewith.

Laying of cable upto 2 cum 25 sqmm on walls surfaces incl. S & F MS saddles with earthing attachment in 10 SWG GI (Hot Dip) Wire, making holes etc. as per recording per-1 damages and painting ----

PAN, GST and Copy of Trade Enlistment Certificate are Mandatory in this regard.

[Signature]
Commissioner/Secretary/Finance Officer
Chandernagore Municipal Corporation

No.IA/Tend/2025-26/194/F/1 (12)

Dated. 11.11.2025

Copy to :-

1. Mayor
2. Dy Mayor
3. MMIC (Street Light / Education / Trade Licence / Health / W.W / Sports / Store & Garage)
4. Commissioner/Secretary/Finance Officer
5. Engineer
6. A. O.
7. SAE (Elect)
8. S.A.-1 Please publish in Office Website.
9. Office Notice Board

[Signature]
Commissioner/Secretary/Finance Officer
Chandernagore Municipal Corporation

Dept


CHANDERNAGORE MUNICIPAL CORPORATION
ESTIMATE

Estimated Cost:- Rs.5,848/-

Date of Completion: 7 days


Name of the work :- Installation of sufficient light from the house of Sipra Das to Ashis Chowdhuri at Brahminpara under Chandernagore Municipal Corporation Under APAS Scheme -- Booth 63 sl no 5


SL No	Description of Work	Qty	Unit	Rate in Rs.	Amount
1	Supply and delivery of 45 watt LED Street Light with pressure die cast aluminium housing, IP66 protection, road way luminarie with high power LED as per the detail technical proposal specification & vendor list attached [Make-Crompton /Philips)/ Havells or equivalent Warranty Period- 7 Years] Ref: Rate Redrive	1	No.	3579.46	3579.46
2	Fixing outdoor type fluorescent/SV/MV light fitting on pole including S&F 40 mm dia x 1.68 mts. long GI Pipe (ISI-Medium) bracket with 40 mmx10 mm thick, MS clamp etc. and providing wiring with 2x1/1.40 PVC insulated and sheathed wire (single core) from loop box at the base of pole to light fitting through pole & bracket (without control switch) including making connections & painting Ref: PWD(Electrical) Schedule 2014, H-5,H(4)	1	No.	1335.00	1335.00
	Sub Total			RS	4,914.46
	Add (@18%) Gst			RS	884.60
	Sub Total			RS	5,799.06
	Add (@1%) Cess			RS	49.14
	Total			Rs	5,848.21
	Say			Rs	5,848


25.09.2025
SAE (ELECTRICAL)

CHANDERNAGORE MUNICIPAL CORPORATION


25/09/25
AE (MECHANICAL)
CHANDERNAGORE MUNICIPAL CORPORATION


25/09/25
COMMISSIONER
CHANDERNAGORE MUNICIPAL CORPORATION


MAYOR
CHANDERNAGORE MUNICIPAL CORPORATION

CHANDERNAGORE MUNICIPAL CORPORATION

ESTIMATE

Dept


Estimated Cost:- Rs.25,780/- 25,819/-


Date of Completion: 7 days


Name of the work :- Installation of iron pole with 45 watt light in front of Arup Kumar Kundu at Sabinara main Road
Under APAS Scheme -- Booth 122_sl no 7_w18

SL No	Description of Work	Qty	Unit	Rate in Rs.	Amount
1	Supplying of Swaged Steel Tubular pole (IS 2713, Pt. II 1980) for following designation and of following dimensions ---- 410-SP-1; 7.0 mtrs: 62.00Kg Ref: UDMA(E/M) (Vol 1) Schedule 2018, page-3,1 (d)	1	No.	5383	4216
2	S/F double arm projected lamp bracket (Single pip bending) of 50mm (2") dia G.I. pipe (ISI medium) of 2.5 mtr long each having 105 degree curvature with reducing socket to be fitted at the top of the pole with bolts, nuts clamps etc. as required Ref: UDMA(E/M) (Vol 1) Schedule 2018, page-5, 23	1	No.	2491	4216
3	Erection of Single Steel tubular pole of length as given below with/without sole plate & Cap etc. in CC foundation (Proportion and dimension indicated below), having 600x600x150 mm thick CC (4:2:1) base block below sole plate/pole with hard jhama metal including CC (6:3:1) muffing 0.30 mts. dia and 0.30 mts. above ground level including 3 mm thick neat cemented finish and GI earth bolt after making drilled holes etc. on pole & carriage of pole upto 1.6 Km from Store to work-site including filling up the excavated earth pit with shifted soil and ramming properly ---- Upto 9.0 mtr. Size 0.6x0.6x1.70 mts Ref: PWD(Electrical) Schedule 2017, H-1, (A)1(a)	1	No.	2835.00	2835.00
4	Extra on items 1 & 2 above, for providing CC (6:3:1) base block (around the pole) dimension 0.45x0.45x0.60 mt. above ground level, neatly cemented finish (3 mm thick), at the base pole (in lieu of CC muffing) suitable for alkathene/ polythene pipe entry as directed for street light wiring, incl. S & F 20cmx15cmx10cm GI Loop box, 16SWG & incl. drilled hole in pole Ref: PWD(Electrical) Schedule 2017, H-1, (A)3(a)(ii)	1	No.	740.00	740.00
5	Painting of Steel Tubular Pole of lengths and no. of coats of paint, as given below with ready mixed paint/primer of approved make, and brand incl. preparation of surface by sand paper/emery paper, cleaning etc. for receiving fresh coat of paint ---- (a) Upto 9.0 mtr. long pole -- (i)1st coat of aluminium paint over 1 coat of RO priming (ii)2nd coat of aluminium paint over 1st coat Ref: PWD(Electrical) Schedule 2017, H-2, (A)4(a)	1	No.	329.00	329.00
6	Supplying of 1.1 KV. Grade PVC insulated Conductor of following cables (make: Polycab/ Gloster/Havells/): 2 core 4sqmm Ref: UDMA(E/M) Schedule 2018, page-13, 1(a)1)	20	Mtr	73.00	1460.00
7	Laying of cable upto 2 core 25 sqmm on wall/surface incl. S & F MS saddles with earthing attachment in 10 SWG GI (Hot Dip) Wire, making holes etc. as necy. mending good damages and painting ---- Ref: PWD(Electrical) Schedule 2017, F-1, 2(a)	20	Mtr	57.00	1140.00

8	Supply and delivery of 45 watt LED Street Light with pressure die cast aluminium housing, IP66 protection, road way luminarie with high power LED as per the detail technical proposal specification & vendor list attached [Make-Crompton /Philips/ Havells Warranty Period- 7 Years]	1	Nos	3579.46	3579.46
	Ref: Rate Redrive				
9	Fixing outdoor type fluorescent/SV/MV light fitting on pole including S&F 40 mm dia x 1.68 mts. long GI Pipe (ISI-Medium) bracket with 40 mmx10 mm thick, MS clamp etc. and providing wiring with 2x1/1.40 PVC insulated and sheathed wire (single core) from loop box at the base of pole to light fitting through pole & bracket (without control switch) including making connections & painting	1	Nos	1335.00	1335.00
	Ref: PWD(Electrical) Schedule 2014, H-5,H(4)				
10	Supplying and fixing 240/415 V MCB of Breaking capacity 10 KA & C characteristics on din rail of existing DBs and necessary connection --- 6-32 A SPN (Standard)	1	No.	444.00	444.00
	Ref: PWD(Electrical) Schedule 2017, D-7/8				
11	Earthing with 50mm dia GI pipe 3.64mm thick x 3.04mtrs long and 1x4SWG GI (Hot Dip) wire (4mtrs long), 13mm dia x 80mm long GI bolts, double nuts, double washers incl. S&F 15mm dia GI pipe protection (1mtr long) to be filled with bitumen partly under the ground level and partly above ground level driven to an average depth of 3.65mts below the ground level as below: by ISI-Medium GI pipe	1	No.	1369.00	1369.00
	Ref:PWD Schedule (Electrical)2017, Page-G-1/ 2(a)				
	Sub Total		RS		21,663.46
	Add (@18%) Gst		RS		3,899.42
	Sub Total		RS		25,562.88
	Add (@1%) Cess		RS		216.63 255.63
	Total		Rs		25,779.52 25818.5
	Say		Rs		25,780 25819


 12-09-2025
 SAE (ELECTRICAL)
 CHANDERNAGORE MUNICIPAL CORPORATION


 12/09/25
 AE (MECHANICAL)
 CHANDERNAGORE MUNICIPAL CORPORATION


 COMMISSIONER
 CHANDERNAGORE MUNICIPAL CORPORATION

MAYOR
 CHANDERNAGORE MUNICIPAL CORPORATION

CHANDERNAGORE MUNICIPAL CORPORATION

ESTIMATE

Line Dept

Estimated Cost:- Rs. 11,696/- 11,714/-

Date of Completion: 7 days

Name of the work :- Installation of light opposite of the house of Kajol Chatterjee at Boral bagan under Chandernagore Municipal Corporation Under APAS Scheme -- Booth 110 sl no:-15 ward 10

SL No	Description of Work	Qty	Unit	Rate in Rs.	Amount
1	Supply and delivery of 45 watt LED Street Light with pressure die cast aluminium housing, IP66 protection, road way luminarie with high power LED as per the detail technical proposal specification & vendor list attached Make-Crompton (LSTS-45-CDL-M)/Philips(BRP273 LED54 CW M2 SLR PSU S2 45 WT)/ Havells (ENDURA CITYLITE PLATPLUS SL 45WLED 757SASYBOPC) Ref: Rate Redrive	2	Nos	3579.46	7158.92
2	Fixing outdoor type fluorescent/SV/MV light fitting on pole including S&F 40 mm dia x 1.68 mts. long GI Pipe (ISI-Medium) bracket with 40 mmx10 mm thick, MS clamp etc. and providing wiring with 2x1/1.40 PVC insulated and sheathed wire (single core) from loop box at the base of pole to light fitting through pole & bracket (without control switch) including making connections & painting Ref: PWD(Electrical) Schedule 2014, H-5, H(4)	2	Nos	1335.00	2670.00
	Sub Total			RS	9,828.92
	Add (@18%) Gst			RS	1,769.21
	Sub Total			RS	11,598.13
	Add (@1%) Cess			RS	98.29
	Total			Rs	11,696.41

115.98 02
11714.11 02

SAE
02.09.2025
SAE (ELECTRICAL)
CHANDERNAGORE MUNICIPAL CORPORATION

AE
02.09.25
AE (MECHANICAL)
CHANDERNAGORE MUNICIPAL CORPORATION

EE
02.09.25
Executive Engineer(Mech.), KMDA
CHANDERNAGORE MUNICIPAL CORPORATION

SE
Superintending Engineer(E/M), KMDA
CHANDERNAGORE MUNICIPAL CORPORATION

COM
COMMISSIONER
CHANDERNAGORE MUNICIPAL CORPORATION

MAYOR
MAYOR
CHANDERNAGORE MUNICIPAL CORPORATION

CHANDERNAGORE MUNICIPAL CORPORATION

ESTIMATE

Line Dept

Estimated Cost:- Rs. 4,189/-

Date of Completion: 7 days

Name of the work :- Installation of light from House of Pulin Mitra to House of Anil Mitra
Chandernagore Municipal Corporation Under
APAS Scheme -- Booth 109 sl no:-10 ward 10

SL No	Description of Work	Qty	Unit	Rate in Rs.	Amount
1	Supply and delivery of 30 watt LED Street Light with pressure die cast aluminium housing, IP66 protection, road way luminarie with high power LED as per the detail technical proposal specification & vendor list attached Make-Crompton (LSTS-30-CDL-M)/Philips (BRP042 P LED30 CW SI PSU GR SPD P4371)/ Havells (ENDURASUNDOWN SL30W LED 757PASYBOPE) Warranty Period- 7 Years] Ref: Rate Redrive	1	No.	2179.46	2179.46
2	Fixing outdoor type fluorescent/SV/MV light fitting on pole including S&F 40 mm dia x 1.68 mts. long GI Pipe (ISI-Medium) bracket with 40 mmx10 mm thick, MS clamp etc. and providing wiring with 2x1/1.40 PVC insulated and sheathed wire (single core) from loop box at the base of pole to light fitting through pole & bracket (without control switch) including making connections & painting Ref: PWD(Electrical) Schedule 2014, H-5,H(4)	1	No.	1335.00	1335.00
Sub Total				RS	3,514.46
Add (@18%) Gst				RS	632.60
Sub Total				RS	4,147.06
Add (@1%) Cess				RS	35.14
Total					4,182.21

41.47 25
4,182.21 4182.53 25

J. Im
02.09.25
SAE (ELECTRICAL)

CHANDERNAGORE MUNICIPAL CORPORATION

AE (MECHANICAL)

CHANDERNAGORE MUNICIPAL CORPORATION

02.09.25
Executive Engineer(Mech.), KMDA
CHANDERNAGORE MUNICIPAL CORPORATION

COMMISSIONER
CHANDERNAGORE MUNICIPAL CORPORATION

Superintending Engineer(E/M), KMDA
CHANDERNAGORE MUNICIPAL CORPORATION

MAYOR
CHANDERNAGORE MUNICIPAL CORPORATION

ESTIMATE

MUNICIPAL CORPORATION


Estimated Cost:- Rs.47,720/-


Date of Completion: 7 days


Name of the work :- Installation of electric pole with light in front of Bidhan Smriti School Under APAS Scheme -- Bootl
121_sl no 5_w18


SL No	Description of Work	Qty	Unit	Rate in Rs.	Amount
1	Supplying of Swaged Steel Tubular pole (IS 2713, Pt. II 1980) for following designation and of following dimensions ---- 410-SP-1; 7.0 mtrs: 62.00Kg Ref: UDMA(E/M) (Vol 1) Schedule 2018, page-3,1 (d)	2	Nos	5383	10766
2	Erection of Single Steel tubular pole of length as given below with/without sole plate & Cap etc. in CC foundation (Proportion and dimension indicated below), having 600x600x150 mm thick CC (4:2:1) base block below sole plate/pole with hard jhama metal including CC (6:3:1) muffing 0.30 mts. dia and 0.30 mts. above ground level including 3 mm thick neat cemented finish and GI earth bolt after making drilled holes etc. on pole & carriage of pole upto 1.6 Km from Store to work-site including filling up the excavated earth pit with shifted soil and ramming properly ---- Upto 9.0 mtr. Size 0.6x0.6x1.70 mts Ref: PWD(Electrical) Schedule 2017, H-1, (A)1(a)	2	Nos	2835.00	5670.00
3	Extra on items 1 & 2 above, for providing CC (6:3:1) base block (around the pole) dimension 0.45x0.45x0.60 mt. above ground level, neatly cemented finish (3 mm thick), at the base pole (in lieu of CC muffing) suitable for alkathene/ polythene pipe entry as directed for street light wiring, incl. S & F 20cmx15cmx10cm GI Loop box, 16SWG & incl. drilled hole in pole Ref: PWD(Electrical) Schedule 2017, H-1, (A)3(a)(ii)	2	Nos	740.00	1480.00
4	Painting of Steel Tubular Pole of lengths and no. of coats of paint, as given below with ready mixed paint/primer of approved make, and brand incl. preparation of surface by sand paper/emery paper, cleaning etc. for receiving fresh coat of paint ---- (a) Upto 9.0 mtr. long pole -- (i) 1st coat of aluminium paint over 1 coat of RO priming (ii) 2nd coat of aluminium paint over 1st coat Ref: PWD(Electrical) Schedule 2017, H-2, (A)4(a)	2	Nos	329.00	658.00
5	Supplying of 1.1 KV. Grade PVC insulated Conductor of following cables (make: Polycab/ Gloster/Havells): 2 core 4sqmm Ref: UDMA(E/M) Schedule 2018, page-13, 1(a)1)	60	Mtr	73.00	4380.00
6	Laying of cable upto 2 core 25 sqmm on wall/surface incl. S & F MS saddles with earthing attachment in 10 SWG GI (Hot Dip) Wire, making holes etc. as necy. mending good damages and painting ---- Ref: PWD(Electrical) Schedule 2017, F-1, 2(a)	60	Mtr	57.00	3420.00

Vendor list attached [Make-Crompton /Philips/ Havells Warranty Period- 7 Years]		2	Nos	3579.46	7158.92
Ref: Rate Redrive					
8	Fixing outdoor type fluorescent/SV/MV light fitting on pole including S&F 40 mm dia x 1.68 mts. long GI Pipe (ISI-Medium) bracket with 40 mmx10 mm thick, MS clamp etc. and providing wiring with 2x1/1.40 PVC insulated and sheathed wire (single core) from loop box at the base of pole to light fitting through pole & bracket (without control switch) including making connections & painting	2	Nos	1335.00	2670.00
Ref: PWD(Electrical) Schedule 2014, H-5,H(4)					
9	Supplying and fixing 240/415V MCB of Breaking capacity 10kA&C characteristics on din rail of existing DBs and necessary connection-- 6-32 A [Legrand / Schneider/ Crabtree]	2	Nos	157.00	314.00
Ref: PWD(Electrical) Schedule 2017, D-6/7					
10	Earthing with 50mm dia GI pipe 3.64mm thick x 3.04mtrs long and 1x4SWG GI (Hot Dip) wire (4mtrs long), 13mm dia x 80mm long GI bolts, double nuts, double washers incl. S&F 15mm dia GI pipe protection (1mtr long) to be filled with bitumen partly under the ground level and partly above ground level driven to an average depth of 3.65mts below the ground level as below: by ISI-Medium GI pipe	2	Nos	1369.00	2738.00
Ref:PWD Schedule (Electrical)2017, Page-G-1/ 2(a)					
Sub Total					
Add (@18%) Gst			RS		39,254.92
Sub Total			RS		7,065.89
Add (@1%) Cess			RS		46,320.81
Total			RS		463.21
Add (@2%) Contingeny			Rs		46,784.01
Total			RS		935.68
			Rs		47,719.69


 23.09.2015
 SAE (ELECTRICAL)
 CHANDERNAGORE MUNICIPAL CORPORATION
 Sub-Asstt. Engineer (Elec.)
 Chandernagore Municipal
 Corporation


 COMMISSIONER
 CHANDERNAGORE MUNICIPAL CORPORATION
 Commissioner
 Chandernagore Municipal
 Corporation


 23/09/25
 AE (MECHANICAL)
 CHANDERNAGORE MUNICIPAL
 CORPORATION
 Asstt. Engineer (Mech.)
 Chandernagore Municipal
 Corporation


 MAYOR
 CHANDERNAGORE MUNICIPAL
 CORPORATION
 Mayor
 Chandernagore
 Municipal Corporation