



CHANDERNAGORE MUNICIPAL CORPORATION

No.IA/Tend/2025-26/189

Dated. 07.11.2025

URGENT NOTICE INVITING QUOTATION:

APAS Fund

Sealed tenders are invited from the experienced, resourceful and interested Vendors/Suppliers/Contractors to complete the work of the following items required for Electric Dept. under the control of this Corporation individually or unanimously. Vendors/Suppliers/Contractors may participate for both individually or unanimously of the following works.

Quotations are to be given on or before 14.11.2025 within 3 p.m. and will be opened on the same day at 3.30 p.m. Rates should be inclusive of all the taxes and other incidental charges if any. In case of accepted tenderers whose rates have been accepted, fails to supply the required items within the stipulated date & time, necessary items will be purchased from the available sources and the difference in cost will be recovered from the tenderers. The Corporation reserves the right to accept or reject any tender without assigning any reason whatsoever.

Sl. No.	Description of the Items	Booth No	Sl. No.	Ward No.	Quantity Required	Rate Required
1.	Installation of bright LED Light with electric pole in front of the house of Sekh Khokon at Kantapukur Sanpukurdhar.	27	03	02	One Job	Entire Work
2.	Installation of bright street light in front of Gourhatty Double Quarter.	169	01	27	One Job	Entire Work
3.	Enhancement of illumination at entrance point of Dharapara.	55	19	07	One Job	Entire Work

Encls: Estimate of all Works are attached herewith.

PAN, GST and Copy of Trade Enlistment Certificate are Mandatory in this regard.

[Signature]
Commissioner/Secretary/Finance Officer
Chandernagore Municipal Corporation

No.IA/Tend/2025-26/189/1 (12)

Dated. 07.11.2025

Copy to :-

1. Mayor
2. Dy Mayor
3. MMIC (Street Light / Education / Trade Licence / Health / W.W / Sports / Store & Garage)
4. Commissioner/Secretary/Finance Officer
5. Engineer
6. A. O.
7. SAE (Elect)
8. S.A.-1 Please publish in Office Website.
9. Rabindra Bhaban
10. Office Notice Board

[Signature]
Commissioner/Secretary/Finance Officer
Chandernagore Municipal Corporation

CHANDERNAGORE MUNICIPAL CORPORATION
ESTIMATE

Estimated Cost:- Rs.32,435/-

Date of Completion: 7 days


Name of the work :- Installation of bright LED Light with electric pole in front of the house of Sekh Khokon at Kantapukur Sanpukurdhar under APAS Scheme -- Booth 27 sl no 3 w 2

SL No	Description of Work	Qty	Unit	Rate in Rs.	Amount
1	Supplying of Swaged Steel Tubular pole (IS 2713, Pt. II 1980) for following designation and of following dimensions ---- 410-SP-9 ; 7.5mtrs: 110Kg Ref: UDMA(E/M) (Vol 1) Schedule 2018, page-3,1 (e)	1	No.	9550	9550
2	Erection of Single Steel tubular pole of length as given below with/without sole plate & Cap etc. in CC foundation (Proportion and dimension indicated below), having 600x600x150 mm thick CC (4:2:1) base block below sole plate/pole with hard jhama metal including CC (6:3:1) muffing 0.30 mts. dia and 0.30 mts. above ground level including 3 mm thick neat cemented finish and GI earth bolt after making drilled holes etc. on pole & carriage of pole upto 1.6 Km from Store to work-site including filling up the excavated earth pit with shifted soil and ramming properly ---- Upto 9.0 mtr. Size 0.6x0.6x1.70 mts Ref: PWD(Electrical) Schedule 2017, H-1, (A)1(a)	1	No.	2835.00	2835.00
3	Extra on items 1 & 2 above, for providing CC (6:3:1) base block (around the pole) dimension 0.45x0.45x0.60 mt. above ground level, neatly cemented finish (3 mm thick), at the base pole (in lieu of CC muffing) suitable for alkathene/polythene pipe entry as directed for street light wiring, incl. S & F 20cmx15cmx10cm GI Loop box, 16SWG & incl. drilled hole in pole Ref: PWD(Electrical) Schedule 2017, H-1, (A)3(a)(ii)	1	Nos	740.00	740.00
4	Painting of Steel Tubular Pole of lengths and no. of coats of paint, as given below with ready mixed paint/primer of approved make, and brand incl. preparation of surface by sand paper/emery paper, cleaning etc. for receiving fresh coat of paint ---- (a) Upto 9.0 mtr. long pole -- (i)1st coat of aluminium paint over 1 coat of RO priming (ii)2nd coat of aluminium paint over 1st coat Ref: PWD(Electrical) Schedule 2017, H-2, (A)4(a)	1	No.	329.00	329.00
5	Supplying of 1.1 KV. Grade PVC insulated Conductor of following cables (make: Polycab/Gloster/Havells): 2 core 4sqmm Ref: UDMA(E/M) Schedule 2018, page-13, 1(a)1)	50	Mtr	73.00	3650.00
6	Laying of cable upto 2 core 25 sqmm on wall/surface incl. S & F MS saddles with earthing attachment in 10 SWG GI (Hot Dip) Wire, making holes etc. as necy. mending good damages and painting ----	50	Mtr	57.00	2850.00

	Ref: PWD(Electrical) Schedule 2017, F-1, 2(a)				
7	Supply and delivery of 45 watt LED Street Light with pressure die cast aluminium housing, IP66 protection, road way luminarie with high power LED as per the detail technical proposal specification & vendor list attached Make-Crompton /Philips / Havells) Warranty Period- 7 Years]	1	No.	3579.46	3579.46
	Ref: Rate Redrive				
8	Fixing outdoor type fluorescent/SV/MV light fitting on pole including S&F 40 mm dia x 1.68 mts. long GI Pipe (ISI-Medium) bracket with 40 mmx10 mm thick, MS clamp etc. and providing wiring with 2x1/1.40 PVC insulated and sheathed wire (single core) from loop box at the base of pole to light fitting through pole & bracket (without control switch) including making connections & painting	1	No.	1335.00	1335.00
	Ref: PWD(Electrical) Schedule 2014, H-5,H(4)				
9	Supplying and fixing 240/415 V MCB of Breaking capacity 10 KA & C characteristics on din rail of existing DBs and necessary connection --- 6-32 A SPN (Standard)	1	No.	444.00	444.00
	Ref: PWD(Electrical) Schedule 2017, D-7/8				
10	Earthing with 50mm dia GI pipe 3.64mm thick x 3.04mtrs long and 1x4SWG GI (Hot Dip) wire (4mtrs long), 13mm dia x 80mm long GI bolts, double nuts, double washers incl. S&F 15mm dia GI pipe protection (1mtr long) to be filled with bitumen partly under the ground level and partly above ground level driven to an average depth of 3.65mts below the ground level as below: by ISI-Medium GI pipe	1	No.	1369.00	1369.00
	Ref:PWD Schedule (Electrical)2017, Page-G-1/ 2(a)				
	Sub Total			RS	26,681.46
	Add (@18%) Gst			RS	4,802.66
	Sub Total			RS	31,484.12
	Add (@1%) Cess			RS	314.84
	Total			Rs	31,798.96
	Add (@2%) Contingency			RS	635.98
	Total			Rs	32,434.94
	Say			Rs	32,435


 17.10.2025
 SAE (ELECTRICAL)
 CHANDERNAGORE MUNICIPAL CORPORATION
 Sub-Asstt. Engineer (Elec
 Chandernagore Municipa
 Corporation


 17/10/20
 COMMISSIONER
 CHANDERNAGORE MUNICIPAL CORPORATION
 Commissioner
 Chandernagore Municipal
 Corporation


 AE (MECHANICAL) 17/10/25
 CHANDERNAGORE MUNICIPAL
 CORPORATION
 Asstt. Engineer (Mech.)
 Chandernagore Municipal
 Corporation

 MAYOR
 CHANDERNAGORE MUNICIPAL
 CORPORATION
 Mayor
 Chandernagore Municipal
 Corporation

CHANDERNAGORE MUNICIPAL CORPORATION

ESTIMATE


Estimated Cost:- Rs.50,864/-


Date of Completion: 7 days


Name of the work :- Installation of bright street light in front of Gourhatty Double Quarter Under
APAS Scheme -- Booth 169 sl no 01 ward-27

SL No	Description of Work	Qty	Unit	Rate in Rs.	Amount
1	Supplying of Swaged Steel Tubular pole (IS 2713, Pt. II 1980) for following designation and of following dimensions --- 410-SP-30 ; 9.0mtrs: 133 Kg Ref: UDMA(E/M) (Vol 1) Schedule 2018, page-3,1 (i)	1	No.	11547	11547
2	S/F double arm projected lamp bracket (Single pip bending) of 50mm (2") dia G.I. pipe (ISI medium) of 2.5 mtr long each having 105 degree curvature with reducing socket to be fitted at the top of the pole with bolts, nuts clamps etc. as required Ref: UDMA(E/M) (Vol 1) Schedule 2018, page-5, 23	1	No.	2491	2491
3	Erection of Single Steel tubular pole of length as given below with/without sole plate & Cap etc. in CC foundation (Proportion and dimension indicated below), having 600x600x150 mm thick CC (4:2:1) base block below sole plate/pole with hard jhama metal including CC (6:3:1) muffing 0.30 mts. dia and 0.30 mts. above ground level including 3 mm thick neat cemented finish and GI earth bolt after making drilled holes etc. on pole & carriage of pole upto 1.6 Km from Store to work-site including filling up the excavated earth pit with shifted soil and ramming properly --- Upto 9.0 mtr. Size 0.6x0.6x1.70 mts Ref: PWD(Electrical) Schedule 2017, H-1, (A)1(a)	1	No.	2835.00	2835.00
4	Extra on items 1 & 2 above, for providing CC (6:3:1) base block (around the pole) dimension 0.45x0.45x0.60 mt. above ground level, neatly cemented finish (3 mm thick), at the base pole (in lieu of CC muffing) suitable for alkathene/ polythene pipe entry as directed for street light wiring, incl. S & F 20cmx15cmx10cm GI Loop box, 16SWG & incl. drilled hole in pole Ref: PWD(Electrical) Schedule 2017, H-1, (A)3(a)(ii)	1	No.	740.00	740.00
5	Painting of Steel Tubular Pole of lengths and no. of coats of paint, as given below with ready mixed paint/primer of approved make, and brand incl. preparation of surface by sand paper/emery paper, cleaning etc. for receiving fresh coat of paint --- (a) Upto 9.0 mtr. long pole -- (i)1st coat of aluminium paint over 1 coat of RO priming (ii)2nd coat of aluminium paint over 1st coat Ref: PWD(Electrical) Schedule 2017, H-2, (A)4(a)	1	No.	329.00	329.00
6	Supplying of 1.1 KV. Grade PVC insulated Conductor of following cables (make: Polycab/ Gloster/Havells): 2 core 4sqmm Ref: UDMA(E/M) Schedule 2018, page-13, 1(a)1)	50	Mtr	73.00	3650.00

7	Laying of cable upto 2 core 25 sqmm on wall/surface incl. S & F MS saddles with earthing attachment in 10 SWG GI (Hot Dip) Wire, making holes etc. as necy. mending good damages and painting ----	50	Mtr	57.00	2850.00
	Ref: PWD(Electrical) Schedule 2017, F-1, 2(a)				
8	Supply and delivery of 90 watt LED Street Light with pressure die cast aluminium housing, IP66 protection, road way luminarie with high power LED as per the detail technical proposal specification & vendor list attached Make-Crompton /Philips/ Havells Warranty Period- 7 Years	2	Nos	6458.04	12916.08
	Ref: Rate Redrive				
9	Fixing outdoor type fluorescent/SV/MV light fitting on pole including S&F 40 mm dia x 1.68 mts. long GI Pipe (ISI-Medium) bracket with 40 mmx10 mm thick, MS clamp etc. and providing wiring with 2x1/1.40 PVC insulated and sheathed wire (single core) from loop box at the base of pole to light fitting through pole & bracket (without control switch) including making connections & painting	2	Nos	1335.00	2670.00
	Ref: PWD(Electrical) Schedule 2014, H-5,H(4)				
10	Supplying and fixing 240/415 V MCB of Breaking capacity 10 KA & C characteristics on din rail of existing DBs and necessary connection --- 6-32 A SPN (Standard)	1	Nos	444.00	444.00
	Ref: PWD(Electrical) Schedule 2017, D-7/8				
11	Earthing with 50mm dia GI pipe 3.64mm thick x 3.04mtrs long and 1x4SWG GI (Hot Dip) wire (4mtrs long), 13mm dia x 80mm long GI bolts, double nuts, double washers incl. S&F 15mm dia GI pipe protection (1mtr long) to be filled with bitumen partly under the ground level and partly above ground level driven to an average depth of 3.65mts below the ground level as below: by ISI-Medium GI pipe	1	Nos	1369.00	1369.00
	Ref:PWD Schedule (Electrical)2017, Page-G-1/ 2(a)				
	Sub Total			RS	41,841.08
	Add (@18%) Gst			RS	7,531.39
	Sub Total			RS	49,372.47
	Add (@1%) Cess			RS	493.72
	Total			Rs	49,866.20
	Add (@2%) Contingency			RS	997.32
	Total			Rs	50,863.52
	Say			Rs	50,864


 17.10.2025
 SAE (ELECTRICAL)
 CHANDERNAGORE MUNICIPAL CORPORATION
 Chandernagore Municipal Corporation


 17/10/25
 COMMISSIONER
 CHANDERNAGORE MUNICIPAL CORPORATION
 Commissioner
 Chandernagore Municipal


 17/10/25
 AE (MECHANICAL)
 CHANDERNAGORE MUNICIPAL CORPORATION
 Asst. Engineer (Mech.)
 Chandernagore Municipal Corporation


 MAYOR
 CHANDERNAGORE MUNICIPAL CORPORATION
 Mayor
 Chandernagore

CHANDERNAGORE MUNICIPAL CORPORATION

ESTIMATE

Estimated Cost:- Rs. 9,474/-

Date of Completion: 7 days

Name of the work :- Enhancement of illumination at entrance point of Dharapara Under
APAS Scheme -- Booth 55 sl no:-19 ward 7

SL No	Description of Work	Qty	Unit	Rate in Rs.	Amount
1	Supply and delivery of 90 watt LED Street Light with pressure die cast aluminium housing, IP66 protection, road way luminarie with high power LED as per the detail technical proposal specification & vendor list attached Make-Crompton /Philips/Havells Warranty Period- 7 Years Ref: Rate Redrive	1	No.	6458.04	6458.04
2	Fixing outdoor type fluorescent/SV/MV light fitting on pole including S&F 40 mm dia x 1.68 mts. long GI Pipe (ISI-Medium) bracket with 40 mmx10 mm thick, MS clamp etc. and providing wiring with 2x1/1.40 PVC insulated and sheathed wire (single core) from loop box at the base of pole to light fitting through pole & bracket (without control switch) including making connections & painting Ref: PWD(Electrical) Schedule 2014, H-5, H(4)	1	No.	1335.00	1335.00
Sub Total					RS 7,793.04
Add (@18%) Gst					RS 1,402.75
Sub Total					RS 9,195.79
Add (@1%) Cess					RS 91.96
Total					Rs 9,287.75
Add (@2%) Contingency					RS 185.75
Total					Rs 9,473.50

S. Lm
17-10-2025
SAE (ELECTRICAL)
CHANDERNAGORE MUNICIPAL CORPORATION
Sub-Assst. Engineer (Elec.)
Chandernagore Municipa-
Corporation

Prayank
17/10/25
AE (MECHANICAL)
CHANDERNAGORE MUNICIPAL
CORPORATION
Asst. Engineer (Mech.)
Chandernagore Municipal
Corporation

S. Lm
17/10/25
COMMISSIONER
CHANDERNAGORE MUNICIPAL CORPORATION
Commissioner
Chandernagore Municipa-
Corporation

[Signature]
MAYOR
CHANDERNAGORE MUNICIPAL
CORPORATION
Mayor
Chandernagore Municipal